



LEGEND:

- ① TOP OF STAKES
- ② MAIN TRUNK
- ③ TREE TIES (6 REQUIRED) 12" APART MIN. NAILED TO STAKES
- ④ APPROVED 10' TREE STAKES (3) PER SPECIFICATIONS
- ⑤ ORIGINAL GRADE
- ⑥ REFER TO STANDARD PLAN 527 FOR IRRIGATION METHOD
- ⑦ CONTAINER ROOT BALL
- ⑧ BACKFILL MIX PER SPECIFICATIONS
- ⑨ 4" BERM TIGHTLY COMPACTED IN PLACE TO FORM WATERING BASIN
- ⑩ PLANTING TABS PER MANUFACTURERS RECOMMENDATIONS
- ⑪ PLANTING PIT TO BE 2 TIMES WIDTH OF ROOT BALL & SAME DEPTH AS THE ROOT BALL
- ⑫ NATIVE SOIL BACKFILL (COMPACTED)

NOTES:

- 1) INSTALL STAKES 12" MINIMUM FROM TREE TRUNK AND/OR OUTSIDE OF ROOTBALL.

SPECIAL DISTRICTS / PARKS AND COMMUNITY SERVICES		DATE	1/10	CITY OF MORENO VALLEY	
APPROVED BY		DIVISION MANAGER INITIAL		PREPARED BY CAPITAL PROJECTS	
 PUBLIC WORKS DIRECTOR/ CITY ENGINEER		 DIVISION MANAGER INITIAL		TRIPLE STAKE TREE ON SLOPE	
				2 of 2	NO. 532B