

THE WORLD LOGISTICS CENTER® SPECIFIC PLAN



 **HIGHLAND**FAIRVIEW
January 30, 2013

TABLE OF CONTENTS

1.0	INTRODUCTION	8
1.1	The World Logistics Center	8
1.2	Specific Plan Vision and Objectives	8
1.2.1	Development Goals	9
1.2.2	Green Building – Sustainable Development	10
1.2.3	Sense of Place	10
1.2.4	Project Infrastructure	11
1.3	Existing Setting	12
1.3.1	Existing Land Use	12
1.3.2	Existing Fault Zones	13
1.4	Specific Plan Overview	14
2.0	LAND USE PLAN	15
2.1	World Logistics Center Land Use Designations	15
2.2	Logistics Development (LD) Category	17
2.2.1	Purpose and Intent	17
2.2.2	Permitted Uses	17
2.2.3	Development Standards	17
2.2.4	Office Space	18
2.2.5	Fire Station Site	19
2.3	Light Logistics (LL) Category	20
2.3.1	Purpose and Intent	20
2.3.2	Permitted Uses	20
2.3.3	Development Standards	20
2.3.4	Office Space	21
2.4	Logistics Support (LS)	22
2.4.1	Purpose and Intent	22
2.4.2	Project Location	22
2.4.3	Permitted Uses	22
2.4.4	Development Standards	23
2.5	Standards and Guidelines For Open Space	23
2.6	Special Edge Treatment Areas	24



3.0	INFRASTRUCTURE PLAN	25
3.1	Circulation	25
3.2	Freeway	26
3.3	Vehicular Circulation	26
3.3.1	Passenger Car and Truck Circulation	26
3.3.2	Arterial Streets	27
3.3.3	Collector Roads	30
3.3.4	Truck Circulation	31
3.3.5	Mass Transit Circulation	34
3.3.6	Emergency Access / Trail Connection	35
3.4	Non Vehicular Circulation	35
3.4.1	Pedestrian Circulation	35
3.4.2	Multi-Use Trails	35
3.4.3	Bicycle Circulation	37
3.5	Utilities	37
3.5.1	Water	37
3.5.2	Sewer	39
3.5.3	Recycled Water	40
3.5.4	Storm Drain	41
3.5.5	Utility Conditions	43
4.0	OFF-SITE DESIGN STANDARDS	48
4.1	Off-Site Architecture	48
4.1.1	Objectives	48
4.1.2	Ground-mounted Equipment	48
4.1.3	Roof-mounted Equipment	48
4.2	Off-site Landscaping	49
4.2.1	Objectives	49
4.2.2	Water Conservation Measures	49
4.2.3	Streetscapes	51
4.2.3.1	General Design Criteria	51
4.2.4	Special Edge Treatment Areas	52
4.2.4.1	Redlands/ Bay / Merwin Edge Screening Criteria	53
4.2.4.2	SR-60 Screening Criteria	57
4.2.4.3	Southern Boundary Screening Criteria	57
4.2.5	Screening Criteria for Interior Roadways	58
4.2.6	Perimeter Plantings	59
4.2.7	Roundabout & Entry Plantings	73
4.2.8	Streetscape Plantings	81
4.2.9	Offsite Plant Selection	87
4.2.10	Off-site Maintenance	89



4.3	Off-site Lighting	90
4.3.1	Objectives	90
4.3.2	Street Lighting	91
4.4	Off-Site Utilities	92
5.0	ON-SITE DESIGN STANDARDS	93
5.1	On-Site Design Standards and Guidelines	93
5.1.1	General Purpose	93
5.1.2	Uses Shall be Developed in Accordance with the Specific Plan	93
5.1.3	Uses Shall be Developed in Accordance with City of Moreno Valley Municipal Codes	94
5.1.4	Subdivision Map Act	94
5.1.5	Water Quality Management Plan	94
5.1.6	Trash and Recyclable Materials	94
5.1.7	Waste Hauling	94
5.1.8	Water Quality Site Design	94
5.1.8.1	General Standards	94
5.1.8.2	Water Quality Management Plan	94
5.1.8.3	Site Design BMPs	96
5.1.8.4	Source Control BMPs	98
5.1.8.5	Treatment Control BMPs	98
5.1.8.6	Infiltration Basin	99
5.1.8.7	Bioretention facility	99
5.1.8.8	Extended Detention Basin	101
5.2	Site Planning Guidelines	102
5.2.1	Overview	102
5.2.2	Design Objectives	102
5.2.3	Sustainable Design	103
5.2.4	Building Location	104
5.2.5	Site Access	105
5.2.6	Vehicular Circulation	106
5.2.7	Parking	106
5.2.8	Pedestrian Circulation	106
5.2.9	Truck Parking	107
5.2.10	Service Areas	107
5.2.11	Grading & Drainage	108
5.2.12	Walls & Fences	108
5.3	On-Site Architecture	111
5.3.1	Objectives	111
5.3.2	Architectural Character	112



5.3.3	Building Heights	113
5.3.4	Building Form and Massing	114
5.3.5	Facades	115
5.3.6	Fenestration	116
5.3.7	Structure	118
5.3.8	Roofs	119
5.3.9	Entrances	120
5.3.10	Materials	121
5.3.11	Other Materials	122
5.3.12	Exterior Colors	123
5.3.13	Design Details	125
5.3.14	Ground-mounted Equipment	126
5.3.15	Roof-mounted Equipment	127
5.3.16	Ancillary Structures	128
5.3.17	Building Appurtenances	128
5.3.18	Cameras	129
5.4	On-Site Landscaping	130
5.4.1	Objectives	130
5.4.2	Water Conservation Measures	130
5.4.3	Landscape Criteria	131
5.4.4	On-Site Landscape Planting	134
5.4.5	Minimum Landscape Setbacks at Buildings	136
5.4.6	Furnishings	137
5.5	On-Site Lighting	138
5.5.1	Objectives	138
5.5.2	General On-Site Lighting Parameters	138
5.5.3	Driveways and Parking Area Lighting	139
5.5.4	Pedestrian Circulation Lighting	139
5.5.5	Architectural Lighting	140
5.5.6	Service Area Lighting	141
5.5.7	Accent Lighting	142
5.6	On-Site Utilities	143
6.0	SUSTAINABILITY	144
7.0	SIGNAGE	146
7.1	Regulating Signage	146
8.0	PROJECT PHASING	147
8.1	Overall Project Phases	147
8.2	Infrastructure Phasing	147



9.0	FINANCING OF IMPROVEMENTS	148
9.1	Capital Financing	148
9.2	Capital Funding	149
9.3	Funding of Maintenance	149
10.0	IMPLEMENTATION	150
10.1	Purpose and Intent	150
10.2	Approvals Required	150
10.3	Development review processes	150
	10.3.1. Subdivisions	150
	10.3.2. Plot Plans	151
	10.3.3. Additional Items	152
11.0	SPECIAL REGULATIONS	153
11.1	Refrigerated Warehouse Space	153
11.2	Engine Restrictions	153
11.3	On-Site Service Vehicles	153
11.4	Property Maintenance Equipment	153
11.5	Continued Agricultural Activities (Right-to-Farm)	153
11.6	Air Quality and Noise Assessment	154
12.0	DEFINITIONS	155



EXHIBITS

Exhibit 1-1	Moreno Valley Regional Map	8
Exhibit 1-2	Specific Plan Area	9
Exhibit 1-3	Surrounding Land Uses	12
Exhibit 1-4	Existing Fault Zones	13
Exhibit 2-1	Land Use Plan	15
Exhibit 2-2	Fire Station Site	19
Exhibit 2-3	Edge Treatment Areas Map	24
Exhibit 3-1	Circulation Plan	25
Exhibit 3-2	Project Entries Plan	26
Exhibit 3-3	Arterial Streets	27
Exhibit 3-4ab	Typical Section Street "A"	28
Exhibit 3-5	Typical Section Street "B"	28
Exhibit 3-6	Typical Section Street "C, D & E"	29
Exhibit 3-7	Typical Section Street "F, G & H"	30
Exhibit 3-8	Truck Routes	31
Exhibit 3-9	Roundabout Diagram	32
Exhibit 3-10	Truck Parking Section	33
Exhibit 3-11	Truck Pullout Diagram	33
Exhibit 3-12	Potential Bus Route	34
Exhibit 3-13	Fire Access	35
Exhibit 3-14	Multi-Use Trail Plan	36
Exhibit 3-15	Bicycle Circulation Plan	37
Exhibit 3-16	Water Facilities Master Plan	38
Exhibit 3-17	Wastewater Service Plan	40
Exhibit 3-18	Recycled Water Plan	41
Exhibit 3-19	Storm Drain Plan	42
Exhibit 3-20	Electrical Utility Plan	44
Exhibit 3-21	Gas Utility Plan	46
Exhibit 4-1	Special Edge Treatment Areas	52
Exhibit 4-2	Edge Exhibit Map	52
Exhibit 4-3	Redlands Boulevard Street Plan – Section A	53
Exhibit 4-4	Redlands Boulevard Street Plan View A	53
Exhibit 4-5	Redlands Boulevard Street Plan – Section B	53
Exhibit 4-6	Redlands Boulevard Street Plan View B	53
Exhibit 4-7	Redlands Boulevard Street Plan – Section C	54
Exhibit 4-8	Redlands Boulevard Street Plan View C	54
Exhibit 4-9	Bay Street Plan – Section D	54
Exhibit 4-10	Bay Street Plan View D	54
Exhibit 4-11	Merwin Street Plan – Section E	55
Exhibit 4-12	Merwin Street Plan View E	55
Exhibit 4-13	Merwin Street Plan – Section F	55
Exhibit 4-14	Merwin Street Plan View F	55



TABLE OF CONTENTS

Exhibit 4-15	Street D Section G and Plan View G	56
Exhibit 4-16	SR-60 between Theodore and Gilman Springs Road Street Plan – Section H	57
Exhibit 4-17	Southern Boundary Street Plan – Section I	57
Exhibit 4-18	Southern Boundary Street Plan View I	57
Exhibit 4-19	Interior Roadways Street Plan -Section Downhill	58
Exhibit 4-20	Interior Roadways Street Plan -Section Uphill	
Exhibit 4-21	Interior Roadways Street Plan -Section Flat	
Exhibit 4-22	Perimeter Planting Map	59
Exhibit 4-23	Roundabout & Entry Planting Map	73
Exhibit 4-24	Streetscape Planting Map	81
Exhibit 4-25	Slope Planting Guideline	87
Exhibit 4-26	Street Lighting	91
Exhibit 5-1	Water Quality Management Diagram	96
Exhibit 5-2	Visitor Parking Plan	105
Exhibit 5-3	Building Height Plan	113
Exhibit 6-1	Off-site Water Management Plan	144
Exhibit 8-1	Phasing Plan	147





Note: The renderings and depictions contained herein illustrate the Developer's general vision and intention for future development. As the project progresses to actual construction, precise plans and design specifications consistent with these illustrations will be submitted to the City of Moreno Valley for review and approval prior to construction.



1.0 INTRODUCTION

1.1 The World Logistics Center

The World Logistics Center is a master-planned development encompassing up to 41.6 million square feet of building area specifically designed to support large-scale logistics operations in a quality business environment.

The World Logistics Center Specific Plan covers 2,710 acres in Rancho Belago California, the eastern portion Moreno Valley, located southerly of SR-60, between Redlands Boulevard and Gilman Springs Road northerly of the San Jacinto Wildlife Area.



Exhibit 1-1 Regional Map *Note All maps and illustrations are shown enlarged in the Appendix.

1.2 Specific Plan Vision and Objectives

The vision for the World Logistics Center is to establish a world class corporate park environment specifically designed to support the unique logistics and operational needs of international companies and corporate users. The World Logistics Center features a clean and contemporary design aesthetic and an efficient, convenient circulation system to provide a highly functional logistics campus.

The objective of the Specific Plan is to establish the zoning criteria that will guide the orderly development of the World Logistics Center project and carry out the goals of the City's General Plan. Included are development standards for integrated site planning, architecture, and landscaping.



These standards establish a consistent design concept that produces a clear image and a sense of prestige, efficiency and integrity for the World Logistics Center and each project within.



Exhibit 1-2 **Specific Plan Area**



1.2.1 Development Goals

The Specific Plan provides planning strategies and development standards created specifically for the property to incorporate its unique advantages, adapt to its constraints, meet the unique needs of a growing logistics industry, provide for the economic growth needs of the City, and create consistent and compatible land uses for the area in an environmentally responsible manner. Development of the World Logistics Center:

- Provides the land use designations and infrastructure plan necessary to support the City's Economic Development Action Plan.
- Establishes Moreno Valley as a prime location for the logistics industry.
- Creates a project that will provide a balanced approach to the City's responsibilities of fiscal viability, economic opportunity and environmental integrity.
- Provides thousands of ongoing employment opportunities.
- Provides thousands of construction job opportunities during the project's build-out phase.
- Establishes architectural and landscape design guidelines for the project.
- Provides appropriate transition between the project and adjacent uses.

1.2.2 Green Building – Sustainable Development

Construction of the World Logistics Center will be in conformance with California’s “Cal-Green” building regulations, the most stringent, environmentally-friendly building code in the United States. Cal-Green is a comprehensive, far-reaching set of regulations which mandate environmentally-advanced building practices and regulations designed to conserve natural resources and reduce greenhouse gas emissions, energy consumption and water use.

In addition to environmentally responsible building design, the project will incorporate sustainable design features to further reduce its environmental footprint, including but not limited to:

- Minimize water use for landscape irrigation.
- Utilize street designs that harvest runoff and channel it into landscape areas instead of storm drains.
- Accommodate the use of alternative means of transportation.
- Use recycled building materials to the extent feasible.
- Use local sources of building materials to the extent feasible.
- Minimize the amount of impervious paved surfaces throughout the project.
- Incorporate on-site storm water capture and infiltration within landscape areas.
- Support alternative fuel use such as CNG / LNG.
- Maximize the use of roof-mounted solar systems or other alternative power systems.

1.2.3 Sense of Place

The Specific Plan provides for the establishment of a strong and unique identity for the World Logistics Center. The Specific Plan guides the establishment of the project’s sense of place by:

- Applying comprehensive, overall project design guidelines for architecture and project landscaping.
- Providing an efficient and simple circulation system specifically designed to accommodate truck circulation.
- Using streetscapes, banners, entry monumentation, and architecture to strengthen the project identity.



1.2.4 Project Infrastructure

The Specific Plan identifies the backbone infrastructure systems needed to serve the project. Preliminary plans illustrate the proposed expansion of water, sewer, drainage and utility facilities. The infrastructure plan also provides for vehicular (passenger, truck and bus) and non-vehicular (bicycle and pedestrian) circulation, including accommodation of a city multi-use trail.

The Specific Plan provides for the establishment of a strong and unique design identity for the World Logistics Center.



1.3 Existing Setting

1.3.1 Existing Land Use

The World Logistics Center Specific Plan covers approximately 2,710 acres within Rancho Belago in eastern Moreno Valley in Riverside County, California. The project area is located southerly of SR-60, between Redlands Boulevard and Gilman Springs Road, north of San Jacinto Wildlife Area. Existing uses include dry-farmed agricultural land, several scattered rural residential properties and a Metropolitan Water District (MWD) water distribution facility.



Exhibit 1-3 *Surrounding Land Uses*

Surrounding land uses include:

- North:** Highland Fairview Corporate Park (including Skechers), SR-60, vineyard and rural residential uses
- South:** Natural gas distribution facilities, San Jacinto Wildlife Area, Lake Perris State Recreation Area
- East:** Vacant hillside (Badlands), scattered residential uses
- West:** Suburban residential development, vacant land



1.3.2 Existing Fault Zones



Exhibit 1-4 Existing Fault Zones



1.4 Specific Plan Overview



The World Logistics Center Specific Plan will guide the orderly development of the World Logistics Center project in carrying out the City's General Plan. Within the Specific Plan, land use designations are identified and design guidelines, regulations, conditions, and programs are included to direct the systematic development of the project. This Specific Plan implements all applicable elements of the General Plan and includes detailed information about the area's infrastructure improvements such as roads, water, sewer, utilities and flood control facilities.

The World Logistics Center Specific Plan has been adopted pursuant to Government Code Section 65450 which grants authority to cities to adopt Specific Plans for purposes of implementing the goals and policies of their General Plans. The Government Code sets forth the minimum requirements and review procedures for specific plans including the provision of a land use plan, infrastructure and public services plan, criteria and standards for development, and implementation measures.

The Specific Plan complies with the City of Moreno Valley's Municipal Code (Chapter 9.13) governing the content of Specific Plans and procedures for their adoption and enforcement.



2.0 LAND USE PLAN

2.1 World Logistics Center Land Use Designations

The World Logistics Center Specific Plan provides for the development of a master-planned project specifically designed to support logistics uses, incorporating landscape and architectural standards, project-wide criteria for streets, drainage, public infrastructure, lighting and signage, and project features responsive to the needs of the logistics industry.

The Specific Plan includes a land use plan providing for four land use designations: Logistics Development (LD), Light Logistics (LL), Logistics Support (LS) and Open Space (OS).



Exhibit 2-1 **Land Use Plan**

A Circulation Plan provides a roadway network that moves cars and trucks into and through the World Logistics Center in a safe, efficient manner. An Infrastructure Plan is included that addresses the current status of local infrastructure services such as water, sewer, storm drain, electricity and telephone/cable TV and outlines the improvements necessary for these systems to serve the World Logistics Center project. Guidelines for landscaping and architectural design are provided to ensure that a distinct consistent aesthetic theme is realized throughout the project. Additionally, the Plan establishes an implementation program that recognizes the uniqueness of the project and the thoroughness of the design standards.



All of these elements function together to create a comprehensive development program to ensure that the World Logistics Center becomes the contemporary standard for logistics campus projects.

Land Use Designations:

Logistics Development - (LD)

The LD designation provides for high-cube logistics warehouse uses consisting of buildings of 500,000 square feet or greater. Warehousing and logistics activities consistent with the storage and processing of manufactured goods and materials prior to their distribution to other facilities are permitted within this category along with facilities for the outdoor storage of trucks, trailers and shipping containers. Ancillary office, employee services and property management facilities are permitted in connection with primary uses. Development standards for the LD category are included in Section 2.2 of this Specific Plan.

Light Logistics - (LL)

The LL designation provides for warehouse uses less than 500,000 square feet in size, self-storage and vehicle storage uses. Development standards for the LL category are included in Section 2.3 of this Specific Plan.

Logistics Support - (LS)

The LS designation is a “floating zone” which provides for the establishment of a single site that will include fueling facilities and limited service commercial uses in support of the World Logistics Center. The exact location and size of this facility will be determined along with the design of the eastern portion of the project in order to optimize its location within the project and to ensure that it will be compatible with the design and aesthetic elements of the Specific Plan. Development standards for the Logistics Support site are included in Section 2.4 of this Specific Plan.

Open Space - (OS)

The OS designation identifies a 75 acre area in the southwestern portion of the site which is a portion of Mt. Russell. The intent of the OS designation is to preserve this area as a permanent Open Space. This area shall comply with the City of Moreno Valley Open Space Standards and permitted uses.



2.2 LOGISTICS DEVELOPMENT (LD) CATEGORY



2.2.1 Purpose and Intent

The LD category is intended to provide for the development of large, high-cube logistics warehouse buildings.

2.2.2 Permitted Uses

- a. High-cube warehouses
- b. Vehicle and container storage (as a separate use or in connection with other permitted uses)
- c. Construction yards within, or immediately adjacent to approved construction sites
- d. Cellular transmission facilities and structures
- e. Public utility uses and structures needed to implement the WLC project
- f. Fire station

2.2.3 Development Standards

- a. Minimum Lot Size – one acre
- b. Minimum Lot Dimensions – width – fifty (50) feet
depth – fifty (50) feet
- c. Minimum Building Size
 1. High-cube logistics uses: 500,000 square feet
 2. All other uses – no minimum
- d. Floor Area Ratio (FAR)
 1. High-cube logistics uses – no minimum; 1.0 FAR maximum.



- e. Building Height
 - 1. Vehicle/container storage uses – maximum twenty five (25') feet
 - 2. High-cube logistics uses – maximum 60' or 80' per Exhibit 5-3
- f. Building Setbacks
 - 1. From street right of way: twenty (20') feet minimum
 - 2. From other property lines: no minimum
 - 3. Adjacent to residentially occupied property: all buildings shall be set back a distance equal to or greater than the height of the building.
 - 4. Adjacent to CDFW-owned property: 250 feet
 - 5. From residentially zoned property: 250 feet
 - 6. Designated emergency access drives and employee / visitor parking areas are permitted in all setback areas.
 - 7. Notwithstanding the above, the minimum building setback from any public street is sixty (60') feet.
- g. Maximum Lot Coverage – None
- h. Landscape Coverage
 - 1. High-cube logistics uses – 10% minimum
 - 2. All other uses – no minimum
- i. Accessory Structure Size – no minimum, no maximum
- j. Accessory Structure Setbacks – same as primary buildings
- k. Legal nonconforming uses: the provisions of Municipal Code Section 9.02.180 "Legal nonconforming uses, improvements and parcels" shall apply.

2.2.4 Office Space

Office space for permitted uses is limited to five percent of the building floor area, unless otherwise approved through the Plot Plan process.



2.2.5 Fire Station Site

A 1.5-acre site for a future fire station is located in the easterly portion of the Specific Plan. The exact location and configuration of the facility will be established in connection with the design and development of adjacent properties. The timing of the need for a fire station in the Specific Plan area will be determined by several factors, including the phasing of WLC development, the construction of other planned fire stations, and the location and size of WLC buildings.

The fire station site will be identified and offered for dedication to the City in connection with the first subdivision for development in the eastern portion of the WLC project. Funds for the construction of buildings and purchase of equipment will be generated by the collection of Development Impact Fees (DIF).




Exhibit 2-2 Fire Station Site



2.3 LIGHT LOGISTICS (LL) CATEGORY



2.3.1 Purpose and Intent

The LL “Light Logistics” designation provides for warehouse buildings and other storage uses and buildings less than 500,000 square feet in size.

2.3.2 Permitted Uses

- a. Warehouses
- b. Self-storage
- c. Vehicle and container storage
- d. Construction yards within, or immediately adjacent to approved construction sites
- e. Cellular transmission facilities and structures
- f. Public utility uses and structures needed to implement the WLC project.

2.3.3 Development Standards

- a. Minimum Lot Size – 2 acres
- b. Minimum Lot Dimension – width – fifty (50) feet
depth – fifty (50) feet
- c. Minimum Building Size– None

- d. Maximum Floor Area Ratio -1.0 FAR
- e. Building Height – sixty (60) feet maximum
- f. Building Setbacks
 - 1. From street right of way: twenty (20) feet minimum
 - 2. From other property lines: no minimum
 - 3. From residentially occupied property: all buildings shall be set back a distance equal to or greater than the height of the building.
 - 4. From residentially zoned property: 250 feet minimum.
 - 5. Designated emergency access drives and employee / visitor parking are permitted in all setback areas.
 - 6. Notwithstanding the above, the minimum building setback from any public street is sixty (60) feet.
- g. Maximum Lot Coverage – None
- h. Landscape Coverage - No Minimum
- i. Accessory Structure Size – no minimum, no maximum
- j. Accessory Structure Setbacks – same as primary buildings
- k. Legal nonconforming uses - the provisions of Municipal Code Section 9.02.180 “Legal nonconforming uses, improvements and parcels” shall apply.

2.3.4 Office Space

Office space for permitted uses is limited to five (5%) percent of the building floor area, unless otherwise approved by the City through the Plot Plan process.



2.4 LOGISTICS SUPPORT (LS) CATEGORY



2.4.1 Purpose and Intent

The LS “Logistics Support” designation provides for support uses for the WLC including fueling facilities and limited commercial uses oriented to truck operators serving the World Logistics Center.

2.4.2 Project Location

The LS site will be located in the easterly portion of the Specific Plan area. The exact location and configuration of the facility will be established in connection with the design and development of adjacent properties, subject to the following criteria. The LS site shall be located:

- a) With frontage on an internal collector street
- b) At least 250 feet from any residentially occupied or zoned property
- c) On a site with adequate size, access, sight distance, and grades to safely accommodate large trucks

2.4.3 Permitted Uses

- a. Motor fuel sales
- b. Retail sales when operated in connection with a primary fuel sales use.
- c. Construction yards within, or immediately adjacent to approved construction sites.
- d. Cellular transmission facilities and structures
- e. Public utility uses and structures needed to implement the WLC project.



2.4.4 Development Standards

- a. Minimum Lot Size – one acre
- b. Minimum Lot Dimension – width – fifty (50) feet
depth – fifty (50) feet
- c. Building Size – no minimum, 3000 sq. ft. maximum
- d. Maximum Floor Area Ratio (FAR) – 1.0 FAR
- e. Building Height – 25 feet maximum
- f. Setbacks – Twenty (20') feet from all property lines except adjacent to residential property where buildings shall be set back a distance equal to or greater than the height of the building.
- g. Maximum Lot Coverage – None
- h. Landscape Coverage - no minimum
- i. Canopies – Fueling areas shall be covered.
- j. Accessory Structure Size – no minimum, no maximum
- k. Accessory Structure Setbacks – same as primary buildings
- l. Prohibited Uses –
 - 1. Vehicle service/ maintenance/ repairs
 - 2. Drive-thru facilities
 - 3. Overnight truck parking
 - 4. Towing services

2.5 STANDARDS AND GUIDELINES FOR OPEN SPACE

All uses and development with the Open Space (OS) designation shall comply with the standards, guidelines and procedures contained in Section 9.06.030 of the Municipal Code.



2.6 Special Edge Treatment Areas

The Specific Plan includes two designated areas where special setbacks, facilities, grading and landscaping will be provided to create buffer areas between the World Logistics Center and adjacent, existing land uses. These edge areas are shown on Exhibit 2-2.

The Redlands/Bay/Merwin edge to the west and southwest of the project is adjacent to existing suburban residential uses. This edge will feature a minimum setback of 250 feet from residential properties westerly of Redlands Blvd. No buildings, truck yards, circulation or storage areas are permitted in this setback area. (Emergency access and property maintenance excluded).

The SJWA edge to the south is adjacent to state-owned open space which is a portion of the San Jacinto Wildlife Area currently in agricultural use. This edge will include a 250 foot setback to any buildings or truck circulation areas, special landscape design and palette, restricted access, and site lighting controls.



Exhibit 2-3 **Special Edge Treatment Areas**




3.0 INFRASTRUCTURE PLAN

The Infrastructure Plan serves as a guide for the development of detailed plans for roadways, domestic water, wastewater, storm water and utilities that will serve the Specific Plan area. The conceptual infrastructure plans generally identify the routes and locations of infrastructure facilities within the project. Subsequent subdivisions and site development permits will establish the exact size and location of all such facilities.

3.1 Circulation

The Circulation Plan provides standards and guidelines that ensure the safe and efficient movement of people and vehicles into and through the World Logistics Center, addressing light trucks and passenger vehicles, heavy trucks, public transit, and non-vehicular circulation (pedestrians and bicycles). The Circulation Plan includes new streets and the extension of existing streets that will be renamed.



*Street D will be designed to prohibit the use of heavy trucks.

Exhibit 3-1 Circulation Plan

Five points of access bring vehicles into the World Logistics Center from surrounding areas. The primary access to the project will be via Theodore Street, with additional accesses at Eucalyptus Avenue, Cactus Avenue and Gilman Springs Road.



3.2 Freeway

State Route 60 (SR-60) runs along the northerly border of the World Logistics Center. Existing interchanges adjacent to the project are located at Redlands Boulevard, Theodore Street and Gilman Springs Road. Theodore Street will be the primary connection to SR-60 for the World Logistics Center.




Exhibit 3-2 **Project Entries**



3.3 Vehicular Circulation

3.3.1 Passenger Car and Truck Circulation

The World Logistics Center is designed to provide easy access to the project via five access points around the site.

A major feature of the plan is a road system that directs all heavy truck traffic to and from SR60 and Gilman Springs Rd eliminating the need to travel through residential areas to the west. Redlands Blvd. south of Eucalyptus Street and Street D are not designated Truck Routes. Street D will be designed to prohibit use by heavy trucks.

The primary truck entry to the site is through the Theodore Street/SR60 interchange. Secondary truck access points are provided at Gilman Spring Road via intersections with "Street B" and "Street C". Access is provided via the Cactus Avenue connection in the southwest portion of the project for

cars and light trucks. No heavy trucks are allowed to use this entry. Redlands Boulevard south of Eucalyptus Avenue allows only passenger vehicle and light truck access as it is not a City-designated truck route.

3.3.2 Arterial Streets

A network of arterial streets serve the World Logistics Center. Their primary function is to serve traffic within the project area, but some provide regional connectivity through the project. Street sections within the project are shown below. Specific design details of these roadways will be determined in subsequent subdivision and site development approvals. Additional Right of Ways may be required for turn lanes. Turn lanes are assumed as necessary in the median.




Exhibit 3-3 Arterial Streets



Street "A"

Street "A" runs north-south through the World Logistics Center. It is a 6-lane and 4-lane divided roadway, with additional widening and lane improvements at its intersection with SR-60, Eucalyptus Avenue and local interior collector streets. These interior intersections will be upgraded with roundabouts, providing for more efficient traffic flow.




Exhibit 3-4a Street "A" Six Lane




Exhibit 3-4b Street "A" Four lane

Street "B"

Street "B" is a 4-lane divided roadway, running east-west through the northerly portion of the World Logistics Center from Gilman Springs Road on the east to existing Eucalyptus Avenue at Street "A" on the west. The City's General Plan shows this street ultimately extending westerly across the City.




Exhibit 3-5 Street "B"



Street “C”

Street “C” is a 4-lane undivided roadway running east-west through the World Logistics Center, intersecting with Gilman Springs Road on the east. Street “C” does not connect with existing Alessandro Boulevard on the west in order to prevent truck traffic from traveling through existing residential neighborhoods. Passenger cars and light trucks heading west use Street “D” to access Cactus Avenue.

Street “D”

Street “D” is a 4-lane undivided north-south roadway connecting existing Cactus Avenue with the westerly internal loop street (Street “E”). The intersection with Street “D” will be designed to prohibit use by large trucks, preventing their travel through adjacent residential neighborhoods. Special design (where possible) and signage will reinforce this restriction.

Street “E”

Street “E” is a 4-lane undivided internal collector road providing direct access to development areas in the westerly portion of the project. Design details of this roadway will be determined by subsequent subdivision and site development approvals.




Exhibit 3-6 Street “C”, “D”, “E”

3.3.3 Collector Roads

Street "F"

Street "F" is a two-lane internal collector road providing direct access to development areas in the central portion of the project. It intersects with Street "A" at its northerly end and with Street "G" at its southerly end. A roundabout is planned at its intersection with Street "C." Specific design details of this roadway will be determined by subsequent subdivision and site development approvals.

Street "G" and "H"

Street "G" and "H" are internal collector roads providing direct access to development areas in the southerly portion of the project. They are 2-lane undivided roadways. Specific design details of this roadway will be determined by subsequent subdivision and site development approvals.




Exhibit 3-7 Street "F", "G", "H"



3.3.4 Truck Circulation

The efficient, safe circulation of large commercial vehicles is a major component of the World Logistics Center Plan. The circulation system is designed to move large vehicles between the regional highway system and the businesses of the World Logistics Center while directing heavy trucks away from nearby residential neighborhoods. The World Logistics Center plan directs all heavy truck traffic to SR-60 and Gilman Springs Road and away from Redlands Boulevard (south of Eucalyptus) and Cactus Avenue. These prohibitions are incorporated in the City's Truck Route Ordinance

Signage and physical barriers, where feasible, will be provided to preclude heavy trucks from using Street "D" to enter or exit the project. The City's Truck Route Ordinance will reinforce these prohibitions.




Exhibit 3-8 **Truck Routes**

Approved truck routes in the area include Theodore Street, Alessandro Boulevard, Redlands Boulevard (north of Eucalyptus), Eucalyptus Avenue and Gilman Springs Road.



The Plan includes three roundabouts for safe and efficient vehicular movement throughout the project. They are located at Street A, Street C, Street E, and Street F. The detailed design of these roundabouts will be reviewed in connection with site specific design projects.




Exhibit 3-9 Roundabout Diagram



Example of Roundabout Circulation



The World Logistics Center Specific Plan prohibits parking on all streets except at designated truck pullout parking lanes. These lanes provide parking areas for vehicles for a limited 3 hour duration when access to project sites is not available. They are designed to be offset from the traffic lanes to allow for unobstructed thru-traffic and shall be located no closer than 200 feet from intersecting street curb return. The locations and detailed designs will be reviewed in connection with subsequent subdivision and site development permits. No pullout lanes will be located on Street 'A'.




Exhibit 3-10 Truck Pullout Diagram




Exhibit 3-11 Truck Parking Section



3.3.5 Mass Transit Circulation

All streets in the World Logistics Center are designed to accommodate bus service. Regional bus service in Western Riverside County is provided by the Riverside Transit Agency (RTA), however they do not currently operate any routes in the immediate vicinity of the World Logistics Center. RTA will determine if and when bus service will be provided. Facilities to support future bus service to the project pursuant to RTA's "Design Guidelines for Bus Transit" will be incorporated, as needed, into street design in connection with site-specific development proposals. Covered shelters shall be provided at all bus stops. A standard design for shelters shall be reviewed and approved by RTA and the City prior to installation of first shelter.




Exhibit 3-12 **Potential Bus Route**

Exhibit 3-12 illustrates a potential bus route that would conveniently serve the majority of building areas within the WLC. This is only a conceptual route. The RTA will determine when bus service will be extended to the WLC area and its route.



3.3.6 Emergency Access / Trail Connection

An emergency access roadway will be provided between Alessandro Blvd. and future Street "D" as shown. This roadway provides access for emergency vehicles between the WLC area and the existing residential neighborhoods to the west. This roadway will also accommodate a combination bikeway / pedestrian way to facilitate non-vehicular circulation within the WLC.



Exhibit 3-13 Fire Access

3.4 Non Vehicular Circulation

3.4.1 Pedestrian Circulation

The World Logistics Center provides a network of pedestrian ways on project streets, as required to comply with ADA and other applicable codes, to connect all areas of the project to surrounding areas and to interconnect all buildings within the project. Details of these pedestrian ways will be determined by subsequent subdivision and site development approvals.

3.4.2 Multi-Use Trails

To provide public trail access to the Lake Perris Recreational Area as well as a connection to the State San Jacinto Wildlife area, an extension of the City's Redlands Blvd multi-use trail will be routed along the east side of Redlands Blvd., the north side of Bay Avenue and the east side of Street D connecting



to the existing trail along the south side of Cactus Ave. From that point the trail heads easterly, through the Open Space area to connect to the SJWA at the former Davis Rd. alignment (See Exhibit 3-11). Details of this trail alignment will be established with site-specific development proposals. The multi-use trails within the World Logistics Center will comply with existing city standards.




Exhibit 3-14 Multi-Use Trail Plan



3.4.3 Bicycle Circulation

Class II bikeways are provided along all roadways within the World Logistics Center. Details of these facilities will be determined by subsequent subdivision and site development approvals. All street improvement plans will include these bikeways.




Exhibit 3-15 **Bicycle Circulation Plan**



3.5 Utilities

3.5.1 Water

Eastern Municipal Water District (EMWD) provides water service to the World Logistics Center, receiving its water from Metropolitan Water District (MWD) and local groundwater wells. The 2009 EMWD Water Facilities Master Plan (Master Plan) in conjunction with the Moreno Valley Water Pressure Zone Realignment Study (Realignment Study) evaluated the existing and future water needs and facilities required for the Moreno Valley Water System. Master Plan and Realignment Study analyzed the existing water system operating pressures and flows and recommended improvements to the system including realignment of the 1764 and 1900 pressure zones to 1764, 1860 and 1967 pressure zones. The area is currently served by existing pipelines in the 1764 and 1900 pressure zones that range in size from 8-inch to 21-inch diameter pipes.

The California Aqueduct/Metropolitan Water District (MWD) owns and operates a transmission line 145 inches in diameter, running north-south through the project area in Street 'A', and east-west in existing Eucalyptus Avenue, east of Street 'A'.




Exhibit 3-16 Water Facilities Master Plan

Development of the proposed project site will require three new water reservoirs to serve each of the respective water pressure zones (1967, 1860 and 1764). Two of the reservoirs are located outside of the Specific Plan boundary.

As development proceeds within the World Logistics Center, new waterlines, ranging in size from 12" to 24", will be constructed in the existing and proposed roadways to connect to future water tanks. The water system will require a new pump station at the 1764 reservoir and an upgrade to the existing pump station near Cottonwood Avenue and Redlands Boulevard. All water facilities will be constructed to EMWD standards and will be subject to a plan of service approval.





Minimize water infrastructure through native and drought tolerant landscapes

3.5.2 Sewer

Eastern Municipal Water District (EMWD) provides wastewater service to The World Logistics Center area. Wastewater generated from the World Logistics Center area will be treated at EMWD's Moreno Valley Regional Water Reclamation Facility (MVRWRF). The MVRWRF, located in the southwestern portion of the City near Kitching Street and Mariposa Avenue, has the capacity to treat 16 million gallons per day (MGD) of wastewater. The primary trunk sewer line serving the World Logistics Center area is located in Redlands Boulevard.

This trunk sewer line continues in a southerly direction in Cactus Avenue, JFK Drive, Iris Avenue and Lasselle Streets conveying wastewater to the MVRWRF.

The proposed sewer in Street "A" and all lines to the west are a gravity system and run generally southwest to a point of connection at Brodiaea Avenue and Redlands Boulevard. As demand requires, the existing segment of sewer in Brodiaea Avenue, west of Redlands Boulevard, will be upsized from a 15" to a 21" line.






Exhibit 3-17 **Wastewater Service Plan**

The sewer system east of Street “A” will flow by gravity to a future sewer lift station at the southerly project boundary. From there, a force main will carry wastewater in a northwest direction, where it joins the gravity system west of Street “A” described above. Sewer lines will be located within public street rights-of-way to the greatest degree possible. Some of the buildings may require individual (private) lift stations due to building lengths, location of buildings, and phasing of improvements.

Future lines will range in size between 8” and 21”, and will be constructed to EMWD standards and will be subject to a plan of service approval.

3.5.3 Recycled Water

As stated in EMWD’s Water Supply Assessment for the World Logistics project, EMWD policy recognizes recycled water as the preferred source of supply for all non-potable water demands, including irrigation of recreation areas, greenbelts, open space common areas, commercial landscaping, and aesthetic impoundment or other water features. The proposed project is near an existing recycled water line and EMWD has indicated that in the future recycled water will be available for the project.



Recycled water will be used on the proposed project to the greatest extent practical. The availability, feasibility and reliability of recycled water use will be included in EMWD’s evaluation of the plan of service for the project.




Exhibit 3-18 Recycled Water Plan

3.5.4 Storm Drain

The World Logistics Center Specific Plan area is within the San Jacinto River watershed which is part of the larger Santa Ana River watershed. The stormwater runoff from the project generally flows in a southerly direction to the San Jacinto River at an average gradient of 1 to 2 percent. A topographic divide located west of Street “A” separates stormwater flows to the San Jacinto River into two sub-areas. Runoff east of the divide flows to the San Jacinto Wildlife Area and the Gilman Hot Springs hydro-subarea. Runoff west of the divide is tributary to the Perris Valley Storm Drain and the Perris Valley hydro-subarea. Both hydro-subareas are tributary to the San Jacinto River, approximately 10 miles south of the project site.

The Riverside County Flood Control and Water Conservation District (RCFCWCD) is the responsible agency for the project area’s regional flood control system. The westerly portion of the project site is located within the Moreno Master Drainage Plan (MMDP). An existing 12-foot by 8-foot reinforced concrete box (RCB) owned by RCFCWCD is located east of



Redlands Boulevard. This facility collects water passing under SR-60 and outlets south of Eucalyptus Avenue where it flows across agricultural land downstream. Further south, the agricultural land drains to a RCFCWCD earthen channel at Redlands Boulevard which flows to a greenbelt channel located north of Cactus Avenue and east of Redlands Boulevard and ultimately drains to the Perris Valley Storm Drain.




Exhibit 3-19 Storm Drain Plan

On the east side of the project site there is no master plan of drainage. The existing drainage facilities consist of open ditches along Theodore Street that convey runoff from adjacent areas and lands northerly of SR-60. A series of existing drainage culverts cross Gilman Springs Road conveying the offsite runoff from the Badlands through the World Logistics Center site.

Based on the latest Flood Insurance Rate Map (FIRM) published by the Federal Emergency Management Agency (FEMA), the project site is not located within a 100-year floodplain.

A system of underground drainage lines and detention basins will convey the stormwater runoff and manage the increased flow due to the proposed development. At each stage of development, the peak flows at downstream discharge points at the southerly project boundary will not exceed the peak flows for the existing condition.



Along the boundary of the San Jacinto Wildlife Area, concentrated flows released from detention basins will be spread to mimic existing sheet flow patterns.

3.5.5 Utility Conditions

Existing Electrical Service

Moreno Valley Utility (MVU) is the electricity provider for the World Logistics Center. MVU has an existing underground electrical service at the intersection of Dracaea Road and Redlands Boulevard. An electrical substation is located west of the project area at the southwest corner of Moreno Beach Drive and Cottonwood Avenue. The substation has a current capacity to distribute 56 Megawatts (MW) of power. The substation was designed for future expansion to an ultimate capacity of 112 MW. The current peak load for this substation is 22 to 26 MW. There is currently a 4 MW surplus capacity available.

SCE has existing 12 kV and 115 kV overhead power lines throughout the project area. The 115 kV power lines are located along Gilman Springs Road, Street B east of Street A, Street A north of Eucalyptus Street and along Brodiaea Avenue/Davis Road to the south. The 12 kV power lines are located along Gilman Springs Road, Theodore Street, Alessandro Boulevard, Eucalyptus Street east of Theodore Street and Redlands Boulevard.

Proposed Electrical Service

Based on electrical demands provided by MVEU and data from other warehouse/distribution projects, the World Logistics Center has an estimated total electrical demand of 147 MW. As development proceeds, the existing electrical substation located at the southwest corner of Moreno Beach Drive and Cottonwood Avenue will be expanded to its planned 112 MW capacity. A new substation will be built within the World Logistics Center area to meet the project's electrical demand at build-out. All MVEU primary distribution conductors within the project will be installed in underground conduit and vaults in the public street right-of-way or easements as a joint trench with telephone, cable TV and natural gas.



Any SCE overhead power pole lines, less than 115kV, that need to be relocated to develop the project will be placed in underground conduits and vaults. SCE facilities 115kV or greater will remain as overhead lines.




Exhibit 3-20 **Electrical Utility Plan**

Existing Natural Gas

Southern California Gas Company (SCGC) is the natural gas provider for the World Logistics Center. A 4" medium pressure service line runs in Redlands Boulevard. Low pressure facilities serve the residential area located west of Redlands Boulevard and southwest of Merwin Street and Bay Avenue.

Throughout the World Logistics Center, natural gas is transmitted through SDG&E underground pipelines serving the Southern California region that range in size from 16 inches to 36 inches. Two 30" diameter transmission pipelines that run in an east-west direction are located north and south of Alessandro Boulevard. Three transmission pipelines, 16", 24" and 36" diameters run in a north-south direction along Virginia Street, south of Alessandro Boulevard. The 36" diameter line also extends east from Virginia Street parallel with the 30" line that runs south of Alessandro Boulevard.

SCGC transmission facilities within the World Logistics Center include a gas line blow-down facility and flow metering station at Alessandro Boulevard and Virginia Street.



Further south on Virginia Street, San Diego Gas & Electric (SDG&E) operates a natural gas compression station, known as the Moreno Compressor Station. It supplies gas to San Diego via 16", 30" and 36" transmission pipelines.

Questar has a 16" natural gas transmission line that runs in Alessandro Boulevard from Gilman Springs Road to Theodore Street, where it turns south to Maltby Avenue, and then turns west to Redlands Boulevard.



San Diego Gas & Electric Natural Gas Compression Station



Proposed Natural Gas Service

SCGC has indicated the 4" medium pressure service line that runs in Redlands Boulevard will be extended into the World Logistics Center to service the development. Gas service will be installed in the public street right-of-way or easements as a joint trench with telephone, cable TV and electrical services.

In connection with the development of the property, relocation of some natural gas transmission lines into public street right-of-way or easements will be necessary. SDG&E's Moreno Compressor Station will remain in place.




Exhibit 3-21 Gas Utility Plan

Existing Cable and Telecommunications

Telecommunications

Verizon provides telephone services to the World Logistics Center area. Underground telephone facilities are located throughout the project area and run along Alessandro Boulevard and Theodore Street. Four existing telecommunication cabinets are located northeast of the intersection of Alessandro Boulevard and Virginia Street. Overhead telecommunication lines run along Redlands Boulevard. Facilities for telephone service will be provided in every public street

Cable Television

Time Warner Cable currently provides cable television to the World Logistics Center and vicinity. Existing overhead cable television facilities serve the residential area located west of Redlands Boulevard and southwest of Merwin Street and Bay Avenue. Within the World Logistics Center underground cable television facilities run along Alessandro Boulevard from Merwin Street to Theodore Street and overhead on Theodore Street to Eucalyptus Avenue. Facilities for cable will be made available to all providers.

Proposed Cable and Telecommunications

As development proceeds, cable and telecommunications facilities located west of Redlands Boulevard will be extended to serve the World Logistics Center project. These facilities will be underground and may be provided by a number of service franchises.



Telecommunication infrastructure is a vital component in supporting global connectivity.



4.0 OFF-SITE DESIGN STANDARDS

These standards shall apply to those portions of the WLC property that are not within development sites. This includes common areas, open space, public areas, streetscapes, etc.

4.1 Off-site Architecture



4.1.1 Objectives

Off-site architecture includes buildings that house infrastructure or public use of facilities that serve the WLC. Architectural design should express the character of a corporate logistic center in a manner that is progressive and enduring. In order to establish a clear, unified image throughout the World Logistics Center, these structures shall follow the guidelines set forth in Section 5.1 of these guidelines. These support buildings shall be designed in an understated and supporting fashion for the World Logistics Center.

4.1.2 Ground-mounted Equipment

All exterior ground-mounted equipment—including, but not limited to, mechanical equipment, electrical equipment, emergency generators, boilers, storage tanks, risers, electrical conduit, gas lines, cellular telephone facilities, and satellite dishes must be screened from on-site and off-site view. Wall-mounted equipment is not allowed.

4.1.3 Roof-mounted Equipment

All roof-mounted equipment—including, but not limited to, mechanical equipment, electrical equipment, storage tanks, cellular telephone facilities, satellite dishes, skylights, vents, exhaust fans, smoke hatches, and



ducts--must be below the top of the parapet or equipment screen. Roof access shall be through roof hatches, not exterior ladders. Roof hatches shall be located so that guardrails at parapets are not required.

4.2 Off-Site Landscaping

4.2.1 Objectives

Landscaping is an important element contributing to the identity and unity of the World Logistics Center. As such, all landscaping for the project shall:

- Promote a pleasant, distinctive, corporate environment
- Augment internal cohesion and continuity within the World Logistics Center
- Enhance the structured design concept of the World Logistics Center
- Promote water conservation.

The landscaping design concept is focused toward:

- Providing a clean, contemporary visual appearance
- Coordinating the landscaping treatment along freeway and surface streets to emphasize the circulation system,
- Coordinating streetscapes within the World Logistics Center to unify its general appearance.
- Coordinating off-site landscaping design continuity among individual development sites within the World Logistics Center.
- Minimize long term maintenance

The following guidelines present parameters for general landscape design, water conservation, and streetscapes. On-site landscaping guidelines are addressed in Section 5.3 of these guidelines.

4.2.2 Water Conservation Measures

The World Logistics Center planting and landscape is designed to minimize reliance on supplemental irrigation. Planting and landscape areas will be designed to capture site runoff storm water and allowed to infiltrate. Select areas may require supplemental irrigation with potable or recycled water. Where these conditions occur, the system must conform to all requirements of the Eastern Municipal Water District and the City of Moreno Valley.



Landscape design should consider the following water conservation measures:

- Direct sheet runoff to median and parkways
- Zero curb infrastructure and water harvesting
- Macro and micro climates, solar exposure, prevailing wind conditions
- Direct rooftop and paved area drainage to bioswales.
- Macro and micro climates, solar exposure, prevailing wind conditions
- Site analysis of seasonal temperature patterns, soils and drainage, grades and slopes
- Use of historical evapotranspiration rates and weather station (CIMIS) data
- Use of planting zones coordinated according to plant type, climatic exposure, soil condition and slope to facilitate use of zoned irrigation systems
- Use of low water or drought tolerant plant species in landscape areas served by potable water
- Audit of water use and certification by a licensed landscape architect that the irrigation system was installed and operates as designed
- Tolerant of periodic inundation from storm water runoff and capture

Irrigation system design should consider the following water conservation measures:

- Use of reclaimed water systems if available and practical
- Use of best available irrigation technology to maximize efficient use of water, including moisture sensors, multi-program electronic timers, rain shutoff devices, remote control valves, drip systems, backflow preventers, pressure reducing valves and matched output sprinkler heads
- Use of gate valves to isolate and shut down mainline breaks,
- Design to meet peak moisture demand of all plant materials within design zones, while avoiding flow rates that exceed in filtration rate of soil
- Design to prevent overspray or discharge onto roadways, non-landscaped areas or adjacent properties
- Timing of irrigation cycles to operate at night when wind, evaporation and people activities are at a minimum

All landscape plans shall be reviewed by Eastern Municipal Water District.



WORLD
LOGISTICS
CENTER®

4.2.3 Streetscapes

Landscaping along public streets is designed to provide a unified appearance along street frontages, to reinforce the street hierarchy, and to establish identities of place, particularly at intersections within the World Logistics Center.

4.2.3.1 General Design Criteria

All landscape design and maintenance within the World Logistics Center shall comply with the Landscape and Water Efficiency Requirements contained in the Municipal Code or these guidelines, whichever imposes a higher design or performance standard.

1. Trees are required along all street frontages according to the criteria for streetscapes given in the following sections.
2. All street trees are to be 24" box size when installed, unless otherwise noted. Trees in other areas shall be 15 gallon minimum in size but 25% of trees shall be minimum 24" box.
3. Landscaping berms along street frontages may be utilized. Maximum slopes may not exceed 2:1.
4. Shrubs along street frontages are to be utilized where possible.
(Minimum size at installation is 5 gallon. Minimum size at installation for grasses is 1 gallon.)



4.2.4 Special Edge Treatment Areas Design Criteria

There are two discrete edge treatment plans in and around the project. The areas are indicated below:



Exhibit 4-1 Special Edge Treatment Areas




Exhibit 4-2 Edge Exhibit Map

(Key map for following exhibits)



WORLD LOGISTICS CENTER®

OFF-SITE DESIGN STANDARDS

4.2.4.1 Redlands/ Bay/ Merwin Screening Criteria

Looking perpendicular to the property line from the sidewalk on the western side of Redlands and Merwin and the southern side of Bay, all but 15' of future buildings to be screened by walls, berms, and/or landscaping.

Redlands Boulevard




Exhibit 4-3 Redlands Blvd. Section A




Exhibit 4-4 Redlands Blvd. Plan View A




Exhibit 4-5 Redlands Blvd. Section B




Exhibit 4-6 Redlands Blvd. Plan View B

These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening.



OFF-SITE DESIGN STANDARDS




Exhibit 4-7 Redlands Blvd. Section C




Exhibit 4-8 Redlands Blvd. Plan View C

Bay Street




Exhibit 4-9 Bay St. Section D




Exhibit 4-10 Bay St. Plan View D

These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening.



WORLD
LOGISTICS
CENTER®

OFF-SITE DESIGN
STANDARDS

Merwin Street




Exhibit 4-11 Merwin St. Section E




Exhibit 4-12 Merwin St. Plan View E




Exhibit 4-13 Merwin St. Section F




Exhibit 4-14 Merwin St. Plan View F



OFF-SITE DESIGN STANDARDS

These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening.

Street D




Exhibit 4-15 Section G



These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening.

4.2.4.2 SR-60 Screening Criteria

SR-60 screening criteria is to screen buildings and trucking areas in a similar manner as the area south of SR60 between Redlands Blvd. and Theodore Street.

SR-60 between Theodore and Gilman Springs Road




Exhibit 4-16 SR-60 Section H

4.2.4.3 Southern Boundary Screening Criteria

Standing on the property line looking southerly north, all trucks and truck dock doors are to be screened by walls and/or landscaping.



Southern Boundary




Exhibit 4-17 Southern Boundary Section I




Exhibit 4-18 Southern Boundary Plan View I

These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening.

4.2.5 Screening Criteria for All Interior Roadways

From the adjacent sidewalk, all trucks and truck dock doors are to be screened by walls and/or landscaping.

All Interior Roadways




Exhibit 4-19 Section, Downhill




Exhibit 4-20 Section, Uphill




Exhibit 4-21 Section, Flat

These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening.



4.2.6 Perimeter Plantings



Exhibit 4-22 **Perimeter Planting Map**

Perimeter Planting Legend:

-  Gilman Springs Rd. & 60 Freeway
-  Redlands Blvd., Bay Ave, Merwin St.
-  CDFG
-  Enlargment Area
-  Signage Location
(Sign reads "Passenger Vehicle Entrance/Exit onto Cactus Permitted. Truck Entrance/Exit onto Cactus Prohibited.")
-  View Simulations



WORLD
LOGISTICS
CENTER®

Redlands Boulevard



Not to scale | This exhibit is a graphic representation of a conceptual design at maturity

Trees (24" box minimum)

- T1. Cercidium 'Desert Museum': Desert Museum Palo Verde
- T2. Pinus eldarica: Afghan Pine or Pinus halepensis: Aleppo Pine or Schinus molle: California Pepper
- T3. Acacia farnesiana: Sweet Acacia

Shrubs / Ground Cover (1 gallon minimum)

- S1. Leucophyllum texanum: Texas Ranger
Eleagnus pungens 'Fruitlandii': Fruitland Silverberry
- S2. Fallugia paradoxa: Apache Plume
Justicia californica: Chuparosa
Senna phyllodinea: Silver Cassia
Simmondsia chinensis: Jojoba
Baileya multiradiata: Desert Marigold
- S3. Acacia redolens 'Desert Carpet': Spreading Acacia
Baccharis 'Starn': Coyote Bush
Myoporum parvifolium 'Putah Creek': Creeping Myoporum
Rosmarinus "Huntington Carpet": Rosemary



**OFF-SITE DESIGN
STANDARDS**



Redlands Blvd. View 1 at Installation



Redlands Blvd. View 1 at Maturity

These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening. "Maturity" - 15 years estimated based on average rainfall and growing seasons. These renderings do not include street trees which will add to the screening effects.



WORLD
LOGISTICS
CENTER®

**OFF-SITE DESIGN
STANDARDS**



Redlands Blvd. View 2 at Installation



Redlands Blvd. View 2 at Maturity

These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening. "Maturity" - 15 years estimated based on average rainfall and growing seasons. These renderings do not include street trees which will add to the screening effects.



WORLD
LOGISTICS
CENTER®

**OFF-SITE DESIGN
STANDARDS**



Redlands Blvd. View 3 at Installation



Redlands Blvd. View 3 at Maturity (15 years)


These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening. "Maturity" - 15 years estimated based on average rainfall and growing seasons. These renderings do not include street trees which will add to the screening effects.



**WORLD
LOGISTICS
CENTER®**

**OFF-SITE DESIGN
STANDARDS**

Bay Street



Not to scale | This exhibit is a graphic representation of a conceptual design at maturity

Trees (15 gal. minimum)

- T1. Cercidium 'Desert Museum': Desert Museum Palo Verde
- T2. Pinus eldarica: Afghan Pine or Pinus halepensis: Aleppo Pine or Schinus molle: California Pepper
- T3. Acacia farnesiana: Sweet Acacia

Shrubs / Ground Cover (1 gallon minimum)

- S1. Leucophyllum texanum: Texas Ranger Elaeagnus
Elaeagnus pungens 'Fruitlandii': Fruitland Silverberry
- S2. Fallugia paradoxa: Apache Plume
Justicia californica: Chuparosa
Senna phyllodinea: Silver Cassia
Simmondsia chinensis: Jojoba
Baileya multiradiata: Desert Marigold
- S3. Acacia redolens 'Desert Carpet': Spreading Acacia
Baccharis 'Starn': Coyote Bush
Myoporum parvifolium 'Putah Creek': Creeping Myoporum



**OFF-SITE DESIGN
STANDARDS**



Bay Street View 1 at Installation



Bay Street View 1 at Maturity (15 years)

These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening. "Maturity" - 15 years estimated based on average rainfall and growing seasons. These renderings do not include street trees which will add to the screening effects.



**WORLD
LOGISTICS
CENTER®**

**OFF-SITE DESIGN
STANDARDS**

Merwin Street



Not to scale | This exhibit is a graphic representation of a conceptual design at maturity

Trees (15 gal. minimum)

- T1. Cercidium 'Desert Museum': Desert Museum Palo Verde
- T2. Pinus eldarica: Afghan Pine or Schinus molle: California Pepper
- T3. Acacia farnesiana: Sweet Acacia

Shrubs / Ground Cover (1 gallon minimum)

- S1. Leucophyllum texanum: Texas Ranger
 Eleagnus pungens 'Fruitlandii': Fruitland Silverberry
- S2. Fallugia paradoxa: Apache Plume
 Justicia californica: Chuparosa
 Senna phyllodinea: Silver Cassia
 Simmondsia chinensis: Jojoba
 Baileya multiradiata: Desert Marigold
- S3. Acacia redolens 'Desert Carpet': Spreading Acacia
 Baccharis 'Starn': Coyote Bush
 Myoporum parvifolium 'Putah Creek': Creeping Myoporum
 Rosmarinus "Huntington Carpet": Rosemary



**OFF-SITE DESIGN
STANDARDS**



Merwin Street View 1 at Installation



Merwin Street View 1 at Maturity (15 years)


These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening. "Maturity" - 15 years estimated based on average rainfall and growing seasons. These renderings do not include street trees which will add to the screening effects.



WORLD
LOGISTICS
CENTER®

**OFF-SITE DESIGN
STANDARDS**

CDFW (Fish & Game)



Not to scale | This exhibit is a graphic representation of a conceptual design at maturity


Trees (15 gal. minimum)

- T1. *Tristania conferta*: Brisbane box
- T2. *Chilopsis linearis*: Desert Willow
- T3. *Platanus racemosa*: California Sycamore
- Populus Fremontii*: Cottonwood (Planted at detention basins / Well adapted to riparian regions of Moreno Valley)

Shrubs / Ground Cover (1 gallon minimum)

- S1. *Baccharis sarathroides*: Desert Broom
- Leucophyllum texanum*: Texas Ranger
- Simmondsia chinensis*: Jojoba
- Lycium andersonii*: Anderson Thornbush
- Celtis pallida*: Desert Hackberry
- S2. *Rosmarinus officinalis* 'Prostratus': Creeping Rosemary





CDFW (Fish & Game) View 1 at Installation



CDFW (Fish & Game) View 1 at Maturity (15 years)


These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening. "Maturity" - 15 years estimated based on average rainfall and growing seasons. These renderings do not include street trees which will add to the screening effects.



WORLD
LOGISTICS
CENTER®

**OFF-SITE DESIGN
STANDARDS**

Gilman Springs Road



Not to scale | *This exhibit is a graphic representation of a conceptual design at maturity*

Trees (24" box minimum)

T1. *Pinus eldarica*: Afghan Pine

Shrubs / Ground Cover (1 gallon minimum)

S1. *Rhus ovata*: Sugar Bush

S2. *Rosmarinus officinalis* 'Prostratus': Creeping Rosemary





Gilman Springs Rd. View 1 at Installation



Gilman Springs Rd. View 1 at Maturity (15 years)


These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening. "Maturity" - 15 years estimated based on average rainfall and growing seasons. These renderings do not include street trees which will add to the screening effects.



WORLD
LOGISTICS
CENTER®

**OFF-SITE DESIGN
STANDARDS**

60 Freeway



Not to scale | This exhibit is a graphic representation of a conceptual design at maturity

**Trees (Palms – 25' brown trunk height,
All Other Trees – 36" box minimum – all matching)**

- T1. Pinus eldarica: Afghan Pine
- T2. Washingtonia robusta: Mexican Fan Palm

Shrubs / Ground Cover (1 gallon minimum)

- S1. Cotoneaster lacteus: Cotoneaster
- S2. Acacia redolens 'Desert Carpet': Spreading Acacia
Rosmarinus "Huntington Carpet": Rosemary



4.2.7 Roundabout & Entry Plantings




Exhibit 4-23 Roundabout & Entry Planting Map

Project Entry / Roundabout Plantings Legend:

- Project Entry (Orientation) / Roundabouts
- Enlargement Area
- Signage Location
(Sign reads "Passenger Vehicle Entrance/Exit onto Cactus Permitted. Truck Entrance/Exit onto Cactus Prohibited.")



Project Entry West (Eucalyptus)



Not to scale This exhibit is a graphic representation of a conceptual design.

Trees (24" box minimum – all matching)


T1. *Tristania conferta*: Brisbane box

Shrubs / Ground Cover (1 gallon minimum)

S1. *Lomandra longifolia* 'Breeze': Dwarf Mat Rush



Project Entry South on Cactus



Not to scale | *This exhibit is a graphic representation of a conceptual design. The actual configuration and geometrics will be detailed with the first applicable development proposal including this area.*

Trees (24" box minimum – all matching)

T1. Crape Myrtle sp. (Match existing on south side of street)

Shrubs / Ground Cover (1 gallon minimum)

S1. Lavender sp. (Match existing on south side of street)

S2. Lomandra longifolia 'Breeze': Dwarf Mat Rush





Project Entry South on Cactus View 1 at Installation



Project Entry South on Cactus View 1 at Maturity


These sections depict varying screening techniques through use of walls, berms and/or landscaping. One or more of these techniques may be used to achieve required screening. "Maturity" - 15 years estimated based on average rainfall and growing seasons. These renderings do not include street trees which will add to the screening effects.



WORLD
LOGISTICS
CENTER®

**OFF-SITE DESIGN
STANDARDS**

Project Entry East (Gilman Springs)



Not to scale | This exhibit is a graphic representation of a conceptual design.

Trees (24" box minimum – all matching)

T1. *Pinus eldarica*: Afghan Pine


Shrubs / Ground Cover (1 gallon minimum)

S1. *Lomandra longifolia* 'Breeze': Dwarf Mat Rush

S2. *Cotoneaster lacteus*: Cotoneaster



Project Entry North (Street A)



Not to scale | This exhibit is a graphic representation of a conceptual design.

Trees (25' brown-trunk height—all matching)

T1. *Washingtonia robusta*: Mexican Fan Palm

Shrubs / Ground Cover (1 gallon minimum)


S1. *Baccharis 'Starn'*: Coyote Bush

S2. *Lomandra longifolia*: 'Breeze': Dwarf Mat Rush



WORLD
LOGISTICS
CENTER®

North Roundabout



Not to scale | This exhibit is a graphic representation of a conceptual design. In connection with any development plan incorporating any or all of the roundabout, a preliminary plan for the entire roundabout shall be reviewed and approved by the City. Detailed plans will be required prior to the approval of Street Improvement Plans.

Trees (25' brown-trunk height--all matching)

T1. Phoenix dactylifera: Date Palm

Shrubs / Ground Cover (1 gallon minimum)

S1. Lomandara longifolia 'Breeze': Dwarf Mat Rush



South Roundabout



Not to scale | This exhibit is a graphic representation of a conceptual design. In connection with any development plan incorporating any or all of the roundabout, a preliminary plan for the entire roundabout shall be reviewed and approved by the City. Detailed plans will be required prior to the approval of Street Improvement Plans.

Trees (25' brown-trunk height--all matching)

T1. Phoenix dactylifera: Date Palm

Shrubs / Ground Cover (1 gallon minimum)

S1. Lomandra longifolia 'Breeze': Dwarf Mat Rush

S2. Baccharis 'Starn': Coyote Bush



4.2.8 Streetscape Plantings




Exhibit 4-24 Streetscape Planting Map

Streetscape Legend:

-  Streets 'B' & Eucalyptus Ave.
-  Street 'A'
-  Streets C, D, E, F, G, H
-  Enlargement Area
-  Signage Location
(Sign reads "Passenger Vehicle Entrance/Exit onto Cactus Permitted. Truck Entrance/Exit onto Cactus Prohibited.")



Street A



Not to scale | *This exhibit is a graphic representation of a conceptual design.*

**Trees (Palms – 25' brown trunk height /
All other trees – 24" box minimum – all matching)**

- T1. *Prosopis chilensis*: Chilean Mesquite
- T2. *Washingtonia robusta*: Mexican Fan Palm

Shrubs / Ground Cover (1 gallon minimum)

- S1. *Muhlenbergia rigens*: Deer Grass
- S2. *Baccharis 'Starn'*: Coyote Bush
- S3. *Aloe vera*: Aloe

Landscape Buffer

See Section 4.2.6 for Plant Palette



**OFF-SITE DESIGN
STANDARDS**

Eucalyptus Street



Not to scale | This exhibit is a graphic representation of a conceptual design.

**Trees (Palms – 25' brown trunk height /
All other trees – 24" box minimum – all matching)**

- T1. *Tristania conferta*: Brisbane Box
- T2. *Pinus eldarica*: Afghan Pine
- T3. *Phoenix dactylifera*: Date Palm

Shrubs / Ground Cover (1 gallon minimum)

- S1. *Myoporum parvifolium* 'Putah Creek': Creeping Myoporum
- S2. *Lomandra longifolia* 'Breeze': Dwarf Mat Rush


Landscape Buffer

See Section 4.2.6 for Plant Palette



**OFF-SITE DESIGN
STANDARDS**

Street B



Not to scale | This exhibit is a graphic representation of a conceptual design.

Trees (24" box minimum – all matching)

T1. *Tristania conferta*: Brisbane Box

Shrubs / Ground Cover (1 gallon minimum)

S1. *Muhlenbergia rigens*: Deer Grass

S2. *Simmondsia chinensis* 'Vista': Compact Jojoba


Landscape Buffer

See Section 4.2.6 for Plant Palette



**OFF-SITE DESIGN
STANDARDS**

Street C, E, F, G, H



Not to scale | This exhibit is a graphic representation of a conceptual design.

Trees (24" box minimum – all matching)

T1. *Prosopis chilensis*: Chilean Mesquite

Shrubs / Ground Cover (1 gallon minimum)

S1. *Muhlenbergia rigens*: Deer Grass

S2. *Simmondsia chinensis* 'Vista': Compact Jojoba


Landscape Buffer

See Section 4.2.6 for Plant Palette



OFF-SITE DESIGN STANDARDS

Street D



Not to scale | This exhibit is a graphic representation of a conceptual design.

Trees (24" box minimum – all matching)

T1. *Prosopis chilensis*: Chilean Mesquite

Shrubs / Ground Cover (1 gallon minimum)

S1. *Muhlenbergia rigens*: Deer Grass

S2. *Simmondsia chinensis* 'Vista': Compact Jojoba

Landscape Buffer


See Section 4.2.6 for Plant Palette



OFF-SITE DESIGN
STANDARDS

4.2.9 Offsite Plant Selection

These plant selections shall apply to those portions of the WLC property that are not within development sites. This includes common areas, open space, public areas, streetscapes, etc. All trees to be 15 gallon, minimum, unless otherwise noted.



OFF-SITE DESIGN STANDARDS

Exhibit 4-25 **Slope Planting Guideline** (From Top: Up-slope, Flat-slope, Down-slope)

Landscape Buffer, Interior Slopes, and Detention Basins Plant List

Trees (15 gallon minimum)

<i>Celtis occidentalis</i>	Common Hackberry
<i>Ebenopsis ebano</i>	Texas Ebony
<i>Pinus halepensis</i>	Aleppo Pine
<i>Populus Fremontii</i>	Cottonwood
<i>Prosopis chilensis</i>	Chilean Mesquite
<i>Prosopis glandulosa</i> 'Maverick'	Thornless Texas Honey Mesquite
<i>Schinus molle</i>	California Pepper

(A) Groundcover (1 gallon minimum)

<i>Acacia redolens</i> 'Desert Carpet'	Spreading Acacia 'Desert Carpet'
<i>Baccharis</i> 'Starn'	Coyote Bush
<i>Myoporum parvifolium</i> 'Putah Creek'	Creeping Myoporum

(B) Shrubs (1 gallon minimum)

<i>Atriplex canescens</i>	Four Wing Saltbush
<i>Atriplex lentiformis</i>	Quail Brush
<i>Baccharis sarothroides</i>	Desert Broom
<i>Celtis pallida</i>	Desert Hackberry
<i>Cordia boissieri</i>	Texas Olive
<i>Dasyliirion wheeleri</i>	Desert Spoon
<i>Elaeagnus Pungens</i> 'Fruitlandii'	Fruitland Silverberry
<i>Eriogonum fasciculatum</i>	Common Buckwheat
<i>Fallugia paradoxa</i>	Apache Plume
<i>Lycium andersonii</i>	Anderson Lycium
<i>Muhlenbergia rigens</i>	Deergrass
<i>Rhus ovata</i>	Sugar Bush
<i>Simmondsia chinensis</i>	Jojoba



4.2.10 Off-Site Maintenance

In general terms, public streets (curb-to-curb) and sidewalks will be maintained by the City. Parkways, slopes, drainage facilities, and common areas will be maintained by a property owners' association.



4.3 Off-Site Lighting



4.3.1 Objectives

Exterior lighting is to be provided to enhance the safety and security of motorists, pedestrians and cyclists.

Lighting is intended to create a night time character that reinforces the image of the World Logistics Center as a quality business location.

Lighting is an important element contributing to the identity and unity of the World Logistics Center.

To reinforce identity and unity, all exterior lighting is to be consistent in height, spacing, color and type of fixture throughout the building site and compatible with the lighting program for the World Logistics Center.

All lighting in the vicinity of the San Jacinto Wildlife Area shall be designed to confine all direct light rays to the project site and avoid the visibility of direct light rays from the wildlife area.



4.3.2 Street Lighting

Street lighting is being coordinated throughout the World Logistics Center. For reference, the following information is given:

1. Along arterial streets, lighting fixtures are to be cut-off type, high pressure sodium luminaries or L.E.D. (as determined by the Public Works Director / City Engineer) mounted on smooth concrete poles thirty (30') feet in height. Both luminaire and pole are to be painted white. The poles are to be located and spaced per City standards to achieve appropriate illumination levels.
2. Along all other public streets, the same fixture and location are to be used, except the height is reduced to twenty-five (25') feet.




Exhibit 4-26 **Street Lighting**



4.4 Off-Site Utilities

4.4.1 Electrical, Telephone, CATV and Similar Service Wires and Cables

All electrical, telephone, CATV and similar service wires and cables shall be installed underground.

4.4.2 Electrical Transmission Lines

Electrical transmission lines less than 115kV shall be installed underground.



5.0. ON-SITE DESIGN STANDARDS



5.1 ON-SITE DESIGN STANDARDS AND GUIDELINES

In order to manage the orderly and consistent development of the World Logistics Center, the following land design standards and guidelines will be applied to all development in the Specific Plan area.

These Design Standards and Guidelines serve to create an eco-friendly, high-quality development and establish a distinctive character for the World Logistics Center project. In reviewing development proposals, these guidelines will be the primary tool used to evaluate proposed site design, architecture, landscaping, and other project features such as lighting and site amenities.

5.1.1 General Purpose

On-site design standards and guidelines are set forth to guide the design, construction, review and approval of all buildings within the World Logistics Center. The goal is to attain the best possible design for each site within the World Logistics Center.

5.1.2 Uses Shall Be Developed In Accordance with the Specific Plan

All properties within the World Logistics Center shall be developed in conformance with this Specific Plan.



5.1.3 Uses Shall Be Developed In Accordance With City of Moreno Valley Municipal Codes

All development will be consistent with the Specific Plan objectives and design guidelines. Details of specific development projects will be determined by subdivisions and site development plans. In the event of a conflict between the Specific Plan and the City of Moreno Valley Municipal Code, the Specific Plan will prevail. If the Specific Plan is silent on a particular subject, the Municipal Code will apply.

5.1.4 Subdivision Map Act

Lots created within the World Logistics Center Specific Plan area shall comply with the Subdivision Map Act and be in conformance with the Specific Plan.

5.1.5 Water Quality Management Plan

All development within the World Logistics Center shall be subject to applicable laws of the State of California regarding water quality.

5.1.6 Trash and Recyclable Materials

All development within the World Logistics Center shall provide enclosures (or compactors) for collection of trash and recyclable materials subject to water quality standards and best management practices.

5.1.7 Waste Hauling

Construction and other waste disposal shall be hauled to a city-approved facility.

5.1.8 Water Quality Site Design

5.1.8.1 General Standards

Refer to NPDES Permit Board Order R8-2010-0033 for complete and current information on water quality management standards. Current requirements can be obtained by visiting the State Water Resource Control Board website at www.swrcb.ca.gov.

5.1.8.2 Water Quality Management Plan

Most developments are required to implement a Water Quality Management Plan (WQMP) in accordance with the NPDES Permit Board Order R8-2010-0033. The WQMP for the Santa Ana Region of Riverside County was approved by the Santa Ana Region Water Quality Control



Board on October 22, 2012. Projects identified as a 'Priority Development project' are required to prepare a Project-Specific WQMP. The MS4 Permit mandates a Low Impact Development (LID) approach to stormwater treatment and management of runoff discharges. The project site should be designed to minimize imperviousness, detain runoff, and infiltrate, reuse or evapotranspire runoff where feasible. LID Best Management Practices (BMPs) should be used to infiltrate, evapotranspire, harvest and use, or treat runoff from impervious surfaces, in accordance with the Design Handbook for Low Impact Development Practices. The project should also ensure that runoff does not create a hydrologic condition of concern. The Regional Water Quality Control Board continuously updates impairments as studies are completed. The most current version of impairment data should be reviewed prior to preparation of the Preliminary and Final Project-Specific WQMP.



Example of Water Quality Feature






Exhibit 5-1 Water Quality Management Diagram



5.1.8.3 Site Design BMPs

Site Design BMPs are intended to create a hydrologically functional project design that attempts to mimic the natural hydrologic regime. In accordance with the Riverside County WQMP, project proponents shall implement Site Design concepts that achieve each of the following:

- Minimize Urban Runoff
- Minimize Impervious Footprint
- Conserve Natural Areas
- Minimize Directly Connected Impervious Areas (DCIAs)

Methods of accomplishing the Site Design concepts include:

- Maximize the permeable area.
- Incorporate landscaped buffer areas between sidewalks and streets.

- Maximize canopy interception and water conservation by preserving existing native trees and shrubs, and planting additional native or drought tolerant trees and large shrubs.
- Use natural drainage systems.
- Where soils conditions are suitable, use perforated pipe or gravel filtration pits for low flow infiltration.
- Construct ponding areas or retention facilities to increase opportunities for infiltration consistent with vector control objectives.
- Minimize the use of impervious surfaces, such as decorative concrete, in the landscape design.
- Sites must be designed to contain and infiltrate roof runoff, or direct roof runoff to vegetative swales or buffer areas, where feasible.
- Where landscaping is proposed, drain impervious sidewalks, walkways, trails, and patios into adjacent landscaping.
- Increase the use of vegetated drainage swales in lieu of underground piping or imperviously lined swales.
- Parking areas may be paved with a permeable surface, or designed to drain into landscaping prior to discharging to the MS4.
- Where landscaping is proposed in parking areas, incorporate landscape areas into the drainage design.



Example of Water Quality Feature



5.1.8.4 Source Control BMPs

Source Control BMPs are also required to be implemented for each project as part of the Final WQMP. Source Control BMPs are those measures which can be taken to eliminate the presence of pollutants through prevention. Such measures can be both non-structural and structural.

Non-structural Source Control BMPs include:

- Education for property owners, operator, tenants, occupants, or employees
- Activity restrictions
- Irrigation system and landscape maintenance
- Common area litter control
- Street sweeping private streets and parking lots
- Drainage facility inspection and maintenance

Structural Source Control BMPs include:

- Stenciling and signage
- Landscape and irrigation system design
- Protect slopes and channels
- Properly design fueling areas, trash storage areas, loading docks, and outdoor material storage areas

5.1.8.5 Treatment Control BMPs

The Treatment Control BMP strategy for the project is to select Low Impact Development (LID) BMPs that promote infiltration and evapotranspiration, including infiltration basins, bioretention facilities, and extended detention basins. Generally infiltration BMPs have advantages over other types of BMPs, including reduction of the volume and rate of runoff, as well as full treatment of all potential pollutants potentially contained in the stormwater runoff. It is recognized however that infiltration may not be feasible on sites with low infiltration rates, or located on compacted engineered fill. If the BMP is considered in a fill condition, and the infiltration surface of the BMP cannot extend down into native soils, or if the BMP is considered in a cut condition, and there is no practicable way to verify infiltration rates at the final BMP elevation, infiltration BMPs will not be used. Prior to final design, infiltration tests shall be performed within the boundaries of the proposed infiltration BMP and at the bottom elevation (infiltration surface) of the proposed infiltration BMP to



confirm the suitability of infiltration. In situations where infiltration BMPs are not appropriate, bioretention and/or biotreatment BMPs (including extended detention basins, bioswales, and constructed wetlands) that provide opportunity for evapotranspiration and incidental infiltration will be considered. Harvest and use BMPs will also be considered as a Treatment Control BMP to store runoff for later non-potable uses. Ponds may be used to collect stormwater runoff for harvest and use.

5.1.8.6 Infiltration Basin

An infiltration basin is a flat earthen basin designed to capture the design capture volume. The stormwater infiltrates through the bottom of the basin into the underlying soil over a 72 hour drawdown period. Flows exceeding the design capture volume must discharge to a downstream conveyance system. Infiltration basins are highly effective in removing all targeted pollutants from stormwater runoff. The use of infiltration basins may be restricted by concerns over groundwater contamination, soil permeability, and clogging at the site. Where this BMP is being used, the soil beneath the basin must be thoroughly evaluated in a geotechnical report since the underlying soils are critical to the basin's long term performance. To protect the basin from erosion, the sides and bottom of the basin must be vegetated, preferably with native or low water use plant species.

In addition, these basins may not be appropriate for the following site conditions:

- Industrial sites or locations where spills may occur
- Sites with very low soil infiltration rates
- Sites with high groundwater tables or excessively high infiltration rates, where pollutants can affect groundwater quality
- Sites with unstabilized soil or construction activity upstream
- On steeply sloping terrain

5.1.8.7 Bioretention Facility

Bioretention facilities are shallow, vegetated basins underlain by an engineered soil media. Health plant and biological activity in the root zone maintain and renew the macro-pore space in the soil and maximize plant uptake of pollutants and runoff. This keeps the BMP from becoming clogged and allows more of the soil column to function as both a sponge (retaining water) and a highly effective and self-maintaining biofilter. In most cases, the bottom of a bioretention



facility is unlined, which also provides an opportunity for infiltration to the extent the underlying onsite soil can accommodate. When the infiltration rate of the underlying soil is exceeded, fully biotreated flows are discharged via underdrains. Bioretention facilities therefore will inherently achieve the maximum feasible level of infiltration and evapotranspiration and achieve the minimum feasible (but highly biotreated) discharge to the storm drain system.

These facilities work best when they are designed in a relatively level area. Unlike other BMPs, bioretention facilities can be used in smaller landscaped spaces on the site, such as:

- Parking islands
- Medians
- Site entrances



Example of Water Quality Feature

Landscaped areas on the site can often be designed as bioretention facilities. This can be accomplished by:

- Depressing landscaped areas below adjacent impervious surfaces, rather than elevating those areas
- Grading the site to direct runoff from those impervious surfaces into the bioretention facility, rather than away from the landscaping
- Sizing and designing the depressed landscaped area as a bioretention facility as described in the Riverside County Low Impact Development BMP Design Handbook





Example of Water Quality Feature

5.1.8.8 Extended Detention Basin

The extended detention basin is designed to detain the design volume of stormwater and maximize opportunities for volume losses through infiltration, evaporation, evapotranspiration, and surface wetting. Additional pollutant removal is provided through sedimentation, in which pollutants can attach to sediment accumulated in the basin through the process of settling. Stormwater enters the basin through a forebay where any trash, debris, and sediment accumulate for easy removal. Flows from the forebay enter the top stage of the basin which is vegetated with native grasses that enhance evapotranspiration, and which is interspersed with gravel-filled trenches that help enhance infiltration. Water that does not get infiltrated or evapotranspired is conveyed to the bottom stage of the basin. At the bottom stage of the basin, low or incidental dry weather flows will be treated through a media filter and collected in a subdrain structure. Any additional flows will be detained in the basin for an extended period by incorporating an outlet structure that is more restrictive than a traditional detention basin outlet. The restrictive outlet extends the drawdown time of the basin which further allows particles and associated pollutants to settle out before exiting the basin, while maximizing opportunities for additional incidental volume losses.





5.2 Site Planning Guidelines

5.2.1 Overview

The World Logistics Center Specific Plan has an overall, coordinated design character that emphasizes a clean, contemporary, straightforward, quality image. This image is expressed in site planning, architecture, landscaping, and lighting.

Architectural design is to be compatible in character, massing and materials throughout The World Logistics Center, while allowing for individual identity and creativity in each project. Landscaping, building design, lighting, and utilities are to be closely coordinated along roadways. Criteria for occupancy, building heights, site planning, architecture, landscaping, and lighting are given in further detail in the following sections.

5.2.2 Design Objectives

The objective of the guidelines is to promote the planned image of a quality business and logistics center. Each site will be developed in a manner that emphasizes a clean, pleasant and contemporary environment, and produces an effect that is consistent and compatible with adjacent sites and development throughout the World Logistics Center.




5.2.3 Sustainable Design

Building in an ecological and resource-efficient manner has many advantages for the environment as well as for building users. Sustainable design reduces pollution and conserves natural resources. The architects and engineers that make contributions to the WLC must understand this and strive to lessen the impact their designs have on the environment.

The following sustainability goals have been set for buildings at the WLC:

- Design buildings to accommodate renewable energy systems where feasible
- Create building forms and landscape that protect patrons and employees from unpleasant climate conditions.
- Use water resources responsibly with a constant effort to minimize the use of potable water
- Incorporate life cycle planning and decision making



The design of each building at the World Logistics Center will pursue these goals, by incorporating design features such as, but not limited to, the following:

Water conservation:

- Low flow faucets and fixtures
- Rain water collection (where practical)
- Native landscape
- Direct and capture low-use irrigation and rainfall runoff to landscaped areas



Energy conservation:

- Building orientation
- Glazing, overhangs, and landscaping to capture and control natural daylight
- High performance glazing
- Use of atriums, skylights and internal courtyards to provide additional daylighting

Natural resource conservation:

- Use of renewable materials where feasible
- The use of building materials with recycled content where feasible

5.2.4 Building Location

Buildings are to be located on each site in a manner that is efficient, appropriate to site conditions, supportive of the overall architectural composition and compatibility with nearby projects and development throughout The World Logistics Center.

5.2.4.1 Buildings should be located to enhance project visibility and identity, while maintaining compatible relationships with adjacent projects and street views.

5.2.4.2 Buildings shall be oriented so that loading and service areas are screened from view from streets and public areas.

5.2.4.3 Buildings shall be arranged to provide convenient access to entrances and efficient on-site circulation for vehicles and pedestrians.

5.2.4.4 Buildings shall be arranged to provide landscaped outdoor plazas or entries.

5.2.4.5 Visitor parking shall be convenient to public building entries, as shown below.

5.2.4.6 Outdoor break areas shall be provided convenient to major office areas.





Example of Plaza Entry




Exhibit 5-2 Visitor Parking Plan



5.2.5 Site Access

Vehicular access to individual sites is limited to minimize disruption of traffic flow. All access to public streets is subject to approval by the City of Moreno Valley.

5.2.6 Vehicular Circulation

Onsite vehicular circulation should be clear and direct. Dead-end parking aisles should be avoided.

5.2.7 Parking

5.2.7.1 Off-street parking shall be provided in accordance with the Municipal Code.

5.2.7.2 Off-street parking shall be provided to accommodate all vehicles associated with the permitted use of each site. On-street parking is prohibited, except in designated truck pull out areas.

5.2.7.3 Designated spaces must be provided in convenient locations for handicap, carpool, alternate fuel vehicles, motorcycles and bicycles as required by the State of California and the City of Moreno Valley.

5.2.7.4 Parking areas for motorcycles and bicycles are to be designed for orderly, uncluttered parking. Bicycle parking areas are to be provided with racks and locking capabilities.

5.2.7.5 The view of parking areas from public streets shall be softened by means of grading and/or landscaping.

5.2.7.6 Parking is prohibited in any required landscaping setback areas.

5.2.7.7 Vehicle parking areas are to be landscaped to provide a shade canopy (50% coverage at maturity) and pleasant appearance. Planters must be large enough to avoid crowding of plant material and damage by vehicles.

5.2.7.8 Parking lots shall comply with the accessible parking standards approved by the City of Moreno Valley.

5.2.8 Pedestrian Circulation

Safe, clear pedestrian circulation must be provided between buildings, parking areas and entries on all sites. Where a pedestrian walkway into the site from the public sidewalk is required, it must be located at driveways or between the street trees using the standard design.





*Example of
Pedestrian
Walkway*

5.2.9 Truck Parking

All truck yards shall be screened from public view per this specific plan.

5.2.10 Service Areas

Service, storage, maintenance, loading and refuse collection areas and similar facilities and uses are to be located out of view of public roadways and buildings on adjacent sites, or screened by architectural barriers.



*Example of Service
Structure*

Service areas may not extend into required building and landscape setback zones.

Service areas should be located and designed so that service vehicles have clear and convenient access and do not disrupt vehicular and pedestrian circulation. No loading or unloading is permitted from public streets.



5.2.11 Grading and Drainage

All project grading shall conform to the Municipal Code. Site grading and drainage shall be designed so that surface drainage is collected and treated before leaving the site.

Site grading shall be designed to be compatible with streetscape grades and to minimize the need for handrails or pedestrian ramps within the site.

Concrete swales in parking lots should be located at the edge of parking spaces and/or curb. Swales are prohibited in the middle of drive aisles. Directing drainage to curb and gutters is preferred over concrete swales.

Run-off from roofs, site, and impervious areas shall be directed to planter areas to minimize run-off.

5.2.12 Walls and Fences

Walls and fences must be designed as an integral part of the overall architectural or landscaping design concept. Walls or fences between the streetside landscaping area and a building are limited to a height of 3'-0".

Refuse enclosure shall be walls not less than 6'-0" high. Planting areas for vines, shrubs, and trees shall be provided at the rear and sides of all enclosures.



Example of Security Fence



Materials

Walls are to be constructed of materials compatible with the overall design character of the building. Walls shall be poured in place concrete. Fences shall be wrought iron or tubular steel. Chain link fencing is permitted only where not visible from streets, sidewalks, public parking areas or public building entries.

Design features may include:

- Varied heights, wall plain offsets, and angles.
- Pilasters or distinctive elements.
- Trim, reveals.
- Minor changes of material and finishes where appropriate.
- Trellis/vine panels, landscape pockets

Walls within Street Side Landscaping Setback

Low-profile parking lot screen walls or garden walls are permitted in street-side landscape area.

Height

Screen walls shall not exceed the height necessary to screen the trucks and dock doors. Pilasters and distinctive elements may exceed this maximum. Special fencing may be allowed along CDFW boundary subject to “plan reviewed and approved by City”.



WORLD
LOGISTICS
CENTER®

Gates Visible From Public Areas

Pedestrian and vehicular access gates visible from public areas (i.e., parking lots, streets, sidewalks, etc.) shall be constructed of durable material, such as tubular steel or a similar material.

Prohibited Materials

Barbed wire, wire, integrated corrugated metal, electronically charged or plain exposed plastic vinyl, concrete/PCC fences are prohibited.



5.3 On-Site Architecture

5.3.1 Objectives

Architectural design should express the character of a corporate logistic center in a manner that is progressive and enduring. Individual creativity and identity are encouraged, but care must be taken to maintain design integrity and compatibility among all projects in order to establish a clear, unified image throughout the World Logistics Center.



Simple Form



Progressive and Enduring



Creativity and Identity



5.3.2 Architectural Character

Architectural character should portray a high quality image in a manner that is both progressive and timeless.

Appropriate Characteristics

- Contemporary, classic, technical style
- Clean, smooth, efficient lines
- Distinctive, but compatible image



Inappropriate Characteristics

- Trendy, historical, residential styles
- Tricky, complicated, arbitrary forms
- Sharp contrast with surroundings



WORLD
LOGISTICS
CENTER®

ON-SITE DESIGN
STANDARDS

5.3.3 Building Heights

To maintain consistent and compatible building mass relationships, building heights are limited to the following (unless otherwise approved):



Exhibit 5-3 **Building Height Plan**

Area A: 60 feet above adjacent grade, including parapets, screens, and architectural features

Area B: 80 feet above adjacent grade, including parapets, screens, and architectural features

Height exceptions may be approved by the Planning Official. Exceptions up to ten (10') additional feet in height may be approved to accommodate special interior uses or screening of special mechanical equipment unique to these facilities. In such cases, up to twenty (20%) percent of the building footprint may exceed the height limit.



WORLD
LOGISTICS
CENTER®

5.3.4 Building Form and Massing

Building design should employ clean, simple, geometric forms and coordinated massing that produce overall unity, scale and interest.

Appropriate Treatment

- Straightforward geometry
- Unified composition
- Expression of floor levels and structure
- Solid parapets



Inappropriate Treatment

- Complicated forms
- Arbitrary, inconsistent composition



5.3.5 Facades

Facades should reflect a coordinated design concept, including expression of building function, structure and scale. Buildings can be designed with a consistent, uniform facade; with the center of the facade emphasized; or with the corners of the facade emphasized.

Appropriate Treatment

- Straightforward, functional design
- Expression of structure
- Unity & scale reinforced through an integrated grid module



Inappropriate Treatment

- Arbitrary, inconsistent forms and decoration
- Uninterrupted, floating horizontals
- Wall-mounted



5.3.6 Fenestration

Fenestration should be defined by function and structure, and should be consistent in form, pattern and color.

Appropriate Treatment

- Functional glass use and patterns
- Glazing delineation by mullions and structure
- Balance of wall and glazed surfaces
- Tinted or lightly reflecting glazing



Inappropriate Treatment

- Arbitrary, decorative glass patterns
- Uninterrupted horizontal glazing
- Highly reflective glass



Glazing Colors

Preferred:	Silver, bronze, blue, green, blue-green ranges
Prohibited:	Black, gold, copper ranges
Other:	Requires specific approval



5.3.7 Structure

Structure should be expressed clearly and consistently.

Appropriate Treatment

- Visible vertical support
- Visible structural base
- Functional, straight-forward elements
- Columns integrated into the facade
- Proper structural scale



Inappropriate Treatment

- Floating horizontal levels
- False, decorative structure
- Undersized or oversized structural components



5.3.8 Roofs

Rooflines should be horizontal.

Appropriate Treatment

- Visible vertical support
- Horizontal planes and parapets
- Varied but proportional parapet height
- Roofing materials hidden from off-site view



Inappropriate Treatment

- Gable, hip and mansard roof forms
- Metal, tile, shingle and shake roofing
- Arbitrary decoration



5.3.9 Entrances

Entrances should be clearly defined and inviting.

Appropriate Treatment

- Articulation and color for identity and interest
- Light, open, inviting aspect
- Entry space sequence
- Recessed, protected doorway
- Integration with overall building form
- Coordinated landscaping



Inappropriate Treatment

- Exaggerated forms and color
- Dark, confined appearance
- Abrupt entry. Flush doorways. Tacked-on entry alcove



5.3.10 Materials

Exterior building materials should be smooth, clean and efficient, with an appearance that is contemporary and technical.

Appropriate Materials

- Smooth, precast or tilt-up concrete
- Smooth metal panel systems
- Tinted or lightly reflective glass



Inappropriate Treatment

- Wood beams and siding, brick, Spanish tile, corrugated metal, rough concrete, or highly reflective glass
- Stucco (unless limited in use, with a smooth troweled surface detailed like concrete)



5.3.11 Other Materials

All other materials, including Drivit[®], concrete masonry, wall tile, glass fiber reinforced concrete and new technology materials must be approved.



5.3.12 Exterior Colors

Exterior building colors are to be selected from the palettes below to maintain compatibility within the World Logistics Center.

Appropriate Treatment

- Concrete or stone should have light, natural finish
- Painted wall surfaces directly facing streets or public areas are to be primarily off-white or light warm shades
- Other colors are permitted on recessed or interior facing wall surfaces, or on special features, reveals or mullions
- Service doors and mechanical screens are to be the same color as the wall



Inappropriate Treatment

- Arbitrary patterns, stripes
- Garish use of color



Primary Wall Colors

Colors for primary exterior walls are to be within the range of colors represented by the following list:

Warm whites

Lorette	Pantone Warm Grey 1C
Trotting	Pantone 4685C
Tracing Paper	Pantone Warm Grey 2U
Slinky	Pantone Warm Grey 1U

Cool whites

A La Mode	Pantone 427C
Windblown	Pantone 428C
Chain Link	Pantone 434C
Carbon	Pantone 434C



WORLD
LOGISTICS
CENTER®

ON-SITE DESIGN
STANDARDS

5.3.13 Design Details

Detailing should be clean, clear and straightforward. Details should reinforce overall design unity, interest and scale.

Appropriate Treatment

- Coordinated mullions and details
- Expression and alignment of structural connections
- Finishes commensurate with building materials
- Coordinated entry spaces and landscaping



Inappropriate Treatment

- Insufficient or excessive detailing
- Inadequate interface between materials
- No indication of scale
- Lack of interest



5.3.14 Ground-mounted Equipment

All exterior ground-mounted equipment—including, but not limited to, mechanical equipment, electrical equipment, emergency generators, boilers, storage tanks, risers, electrical conduit, gas lines, cellular telephone facilities, and satellite dishes must be screened from on-site and off-site view. Wall-mounted equipment is not allowed.

Appropriate Treatment

- Ground equipment hidden by screen walls or landscaping
- Screen walls of same or similar material as building walls
- Vines, shrubs, trees on rear and sides of enclosure



Inappropriate Treatment

- Screen material contrasting with adjacent surfaces
- Wood or chain link fencing
- No planting areas for vines, shrubs, and trees, at the rear or sides of walled enclosures



5.3.15 Roof-mounted Equipment

All roof-mounted equipment—including, but not limited to, mechanical equipment, electrical equipment, storage tanks, cellular telephone facilities, satellite dishes, skylights, vents, exhaust fans, smoke hatches, and ducts—must be below the top of the parapet or equipment screen. Roof access shall be through roof hatches, not exterior ladders. Roof hatches shall be located so that guardrails at parapets are not required.

Appropriate Treatment

- Rooftop equipment hidden from off-site view by building parapet or equipment screen
- Rooftop screens fully integrated into architecture



Inappropriate Treatment

- Rooftop equipment extending above parapet or screen
- One-sided rooftop screens that do not hide the equipment from view from secondary streets or from adjacent sites
- Rooftop screens too close to parapet
- Rooftop screens not related to building geometry
- Wood rooftop screens



5.3.16 Ancillary Structures

On a case by case basis, additional buildings may be required to house functions for the proper operation of the facility. The design guidelines found herein apply to all structures regardless of the time of construction, location on site, or use they contain.

5.3.17 Building Appurtenances

On a case by case basis, the proper functioning of a facility may require a piece of equipment, ductwork, shaft, conveyance mechanism, etc. to be physically added to the side of the main building. These appurtenances must comply with the guidelines stated herein to allow for aesthetic continuity.



*Example of a
Building
Appurtenance*



5.3.18 Cameras

The location, appearance, and installation of exterior security cameras must be integrated with the architecture. The top of any roof-mounted camera must be below the top of the parapet to be screened from view of the ground. Parapet-mounted cameras are not allowed. Exposed wires are not allowed. The color of the camera housing must match the color of the poles or the building wall. The color of the camera globe must be clear.

Appropriate Treatment

- Cameras mounted on poles in parking lot (preferred)
- Cameras suspended from soffits (second choice)
- Cameras mounted on building walls with the top of the camera below the top of the parapet (third choice)



Inappropriate Treatment

- Wall-mounted cameras with the top of the camera above the top of the parapet
- Black camera globes
- Exposed wires
- Parapet-mounted cameras
- Roof-mounted cameras visible from the ground
- Cameras mounted in spheres on arms projecting from building walls.



5.4 On-Site Landscaping

5.4.1 Objectives

Landscaping is an important element contributing to the identity and unity of the World Logistics Center. As such, all landscaping for the project shall:

- Promote a pleasant, distinctive, corporate environment
- Augment internal cohesion and continuity within the World Logistics Center
- Enhance the structured urban design concept of the World Logistics Center
- Promote water conservation

The landscaping design concept is focused toward:

- Providing a clean, contemporary visual appearance
- Coordinating the landscaping treatment along freeway and surface streets to emphasize the circulation system
- Coordinating streetscapes within the World Logistics Center to unify its general appearance
- Coordinating on-site landscaping design continuity among individual development sites within the World Logistics Center

The following guidelines present parameters for general landscape design, water conservation, streetscapes, and on-site landscaping.

5.4.2 Water Conservation Measures

The World Logistics Center planting and landscape is designed to minimize reliance on supplemental irrigation. Landscaped areas are to be designed to capture rainfall runoff and tolerate periodic inundation. Select areas may require supplemental irrigation to compensate for seasonal fluctuations. Where these conditions occur, the system must conform to all requirements of the Eastern Municipal Water District and the City of Moreno Valley.

Landscape design should consider the following water conservation measures:

- Macro and micro climates, solar exposure, prevailing wind conditions
- Site analysis of, seasonal temperature patterns, soils and drainage, grades and slopes
- Use of historical evapotranspiration rates and weather station (CIMIS) data



- Capture of rainfall runoff from roofs and impervious area
- Use of planting zones coordinated according to plant type, climatic exposure, soil condition and slope to facilitate use of zoned irrigation systems
- Use of low water or drought tolerant plant species in landscape areas
- Audit of water use and certification by a licensed landscape architect that the irrigation system was installed and operates as designed

Irrigation system design should consider the following water conservation measures:

- Use of reclaimed water systems if available and practical
- Use of best available irrigation technology to maximize efficient use of water, including moisture sensors, multi-program electronic timers, rain shutoff devices, remote control valves, drip systems, backflow preventers, pressure reducing valves and matched output sprinkler heads
- Use of gate valves to isolate and shut down mainline breaks
- Design to meet peak moisture demand of all plant materials within design zones, while avoiding flow rates that exceed infiltration rate of soil
- Design to prevent overspray or discharge onto roadways, non-landscaped areas or adjacent properties
- Timing of irrigation cycles to operate at night when wind, evaporation and people activities are at a minimum
- Allow for periodic inundation from rainfall runoff and capture

5.4.3 Landscape Criteria

Onsite landscaping is to be coordinated in a manner that enhances overall continuity of development in the World Logistics Center, while providing for the individual identity and needs of each project within. The design must address the following criteria.


- Landscaping should be used to reinforce site planning principles, such as using trees to define parking lots and drive aisles
- Plant materials for on-site landscaping are to be selected from the Plant Selection List, Section 5.3.
- Flexibility in the choice of plant materials is limited along street frontages and site perimeters to enhance landscaping coordination along common frontages, but increases toward the site interior to accommodate individual design



- Parking area trees are to be provided at a minimum ratio of one tree per six parking stalls. Tree planters in parking areas shall have a minimum dimension of six feet clear; five feet clear at diamonds. Tree planter fingers must be provided in parking areas to mitigate large uninterrupted areas of paving. Landscaping in parking areas shall comply with the standards contained in the Municipal Code.
- Planting areas for vines, shrubs, and trees is required at the rear and sides of walled enclosures, including trash enclosures.
- Comprehensive planting, including trees, is required along all screen walls, buildings and site perimeters.
- All projects which include designated truck loading areas shall screen such areas from view from adjacent public streets and from onsite visitor parking and building entry areas (palm courts). Such screening shall be accomplished with solid block walls and opaque metal gates.
- Landscaping within truck loading areas, not visible from public view, shall be designed to be sustainable without artificial irrigation, relying on rainfall and runoff from adjacent impervious surfaces (i.e. truck yards and building roofs). The landscape design shall also incorporate sustainable techniques to capture and direct rainfall runoff to these landscaped areas. These areas may include slopes, water quality basins and drainage facilities. Rock or organic mulch shall be placed between plantings to provide coverage and erosion protection.
- Landscaping in visitor parking areas, palm courts and any other areas visible from public view shall have a higher level of landscape treatment and shall utilize an automatic irrigation system to maintain the desired level of landscape appearance. The landscape design shall incorporate sustainable design techniques to capture and direct rainfall runoff to landscape areas, reducing the need for supplemental irrigation.



Palm Court



Not to scale | *This exhibit is a graphic representation of a conceptual design at maturity.*

Trees (Palms – 25' brown trunk height / All other trees – 24" box minimum)

T1. Phoenix dactylifera: Date Palm

T2. See section 5.4.4 for plant list

Shrubs / Groundcover (1 gallon minimum)

S1. Muhlenbergia rigens: Deer Grass

S2. See section 5.3.4 for plant list



5.4.4 On-Site Landscape Planting

All trees to be 15 gallon, minimum, unless otherwise noted. Any additional plants may be proposed, but must be approved by the World Logistics Center Committee.

Trees

Acacia aneura	Mulga
Acacia farnesiana	Sweet Acacia
Caesalpinia cacalaco	Cascalote
Celtis occidentalis	Common Hackberry
Cercidium 'Desert Museum'	Desert Museum Palo Verde
Chilopsis linearis	Desert Willow
Ebenopsis ebano	Texas Ebony
Olea europaea	Olive
Phoenix dactylifera	Date Palm
Pinus brutia var. Eldarica	Afgan Pine
Pinus halepensis	Aleppo Pine
Populus Fremontii	Cottonweed Tree
Prosopis alba	Argentine Mesquite
Prosopis chilensis	Chilean Mesquite
Prosopis glandulosa	Texas Honey Mesquite
Prosopis glandulosa 'Maverick'	Thornless Texas Honey Mesquite
Schinus molle	California Pepper
Tristania conferta	Brisbane Box
Washingtonia filifera	California Fan Palm
Washingtonia robusta	Mexican Fan Palm

Shrubs / Groundcover

Abutilon palmeri	Indian Mallow
Acacia greggii	Catclaw Acacia
Acacia redolens 'Desert Carpet'	Spreading Acacia 'Desert Carpet'
Aloe spp.	Aloe
Atriplex canescens	Four Wing Saltbush
Atriplex lentiformis	Quail Bush
Baccharis sarothroides	Desert Broom
Baccharis 'Starn'	Coyote Bush
Caesalpinia pulcherrima	Redbird of Paradise
Calliandra californica	Baja Fairy Duster
Celtis pallida	Desert Hackberry
Cordia boissieri	Texas Olive
Dasyllirion wheeleri	Desert Spoon
Encelia farinosa	Desert Encelia
Fallugia paradoxa	Apache Plume
Hyptis emoryi	Desert Lavender
Isomeris arborea	Bladderpod
Justicia californica	Chuparosa
Leucophyllum texanum	Texas Ranger
Lycium andersonii	Anderson Lycium



WORLD
LOGISTICS
CENTER®

ON-SITE DESIGN
STANDARDS

Rhus ovata
Salvia greggii
Senna nemophila
Senna phyllodinea
Simmondsia chinensis

Perennials and Grasses

Asclepias subulata
Baileya multiradiata
Eriogonum fasciculatum
Penstemon eatoni
Penstemon parryi
Sphaeralcea ambigua
Muhlenbergia rigens
Nolina parryi

Sugar Bush
Autumn Sage
Desert Cassia
Silver Cassia
Jojoba

Desert Milkweed
Desert Marigold
Common Buckwheat
Firecracker Penstemon
Parry Penstemon
Desert Globe Mallow
Deer Grass
Parry Beargrass



5.4.5 Minimum Landscape Setbacks at Buildings

If parking or access drives are located between any building and a public street frontage, a 15-foot minimum landscaping area is required between the parking or drive aisle and the building. On other sides of the building, a 10-foot minimum landscaping area is required between the parking or drive aisle and the building, except in loading areas.





1. A minimum landscape zone of fifteen (15) feet is required along building perimeters facing a roadway frontage.
2. A minimum landscape zone of ten (10) feet is required along all other building perimeters except loading areas.
3. A minimum landscape zone of five (5) feet is required along all internal property lines.
4. A minimum level landscape zone of eight (8) feet is required on screen walls parallel to and facing the street.

Note: If perpendicular parking spaces are located adjacent to the minimum landscape zone, then a 2'-6" minimum parking overhang is required in addition to the above measurements (17'-6", 12'-6" and 7'-6" respectively).

Trees along screen walls, buildings and site perimeters are required at a minimum average spacing of 1 tree per 30 linear feet of perimeter, planted at fifteen (15) feet or half (1/2) the tree canopy spread from the face of building.





Left: Landscape Setbacks on Slopes
 Right: Landscape Setbacks from Face of Building.

5.4.6 Furnishings

Site Furnishings

Site furnishings such as benches, tables, trash receptacles, planters, tree grates, kiosks, drinking fountains, and other pedestrian amenities should be integral elements of the building and landscape design, and placed at building entrances, open spaces and other pedestrian areas to create a pedestrian friendly environment. Site furnishings should not block pedestrian access or visibility to plazas, open space areas and/or building entrances and should be made of durable, weather-resistant materials.



Example of Site Furniture



5.5 On-Site Lighting

5.5.1 Objectives

Exterior lighting is to be provided to enhance the safety and security of motorists, pedestrians and cyclists.

Lighting is intended to create a nighttime character that contributes to the identity and unity of the World Logistics Center as a quality business location.

To reinforce identity and unity, all exterior lighting is to be consistent in height, spacing, color and type of fixture throughout the building site.

All lighting in the vicinity of the San Jacinto Wildlife Area shall be designed to confine all direct light rays to the project site and avoid the visibility of direct light rays from the wildlife area.

5.5.2 General On-Site Lighting Parameters

To ensure consistency throughout the World Logistics Center, on-site lighting must conform to the overall lighting parameters for the World Logistics Center, including the following:

- 5.5.2.1 Onsite lighting includes lighting for parking areas, vehicular and pedestrian circulation, building exteriors, service areas, landscaping, security and special effects.
- 5.5.2.2 All exterior on-site lighting must be shielded and confined within site boundaries. No direct rays or glare are permitted to shine onto public streets or adjacent lots.
- 5.5.2.3 Lighting fixtures are to be of clean, contemporary design.
- 5.5.2.4 Lighting must meet all requirements of the City of Moreno Valley.
- 5.5.2.5 Tilted wall fixtures (i.e. light fixtures which are not 90 degrees from vertical) are not permitted. Lights mounted to the roof parapet are not permitted. Wall-mounted light fixtures used to illuminate vehicular parking lots are not permitted.





5.5.2.6 Wall-mounted utility lights that cause off-site glare are not permitted. "Shoebox" lights are preferred.

5.5.3 Driveways and Parking Area Lighting

5.5.3.1 All driveways and parking lot lighting shall have zero cut-off fixtures (i.e. the lens is not visible from an angle). Pole height for typical lots shall be as follows:

• Driveways	25' Maximum
• Parking Area	20' Maximum



5.5.3.2 Pole bases in paved areas shall be above grade. They may be round or square. Pole bases in planting areas may be no higher than 6 inches above grade.

5.5.3.3 Both luminaire and pole are to be white.


5.5.3.4 All luminaires shall be metal halide or L.E.D.

5.5.4 Pedestrian Circulation Lighting

5.5.4.1 Pedestrian walkways and building entries will be illuminated to provide for pedestrian orientation and to clearly identify a secure route between parking areas and points of entry to the building.

5.5.4.2 Walkway lighting must have zero cut-off fixtures mounted at a uniform height no more than eight (8) feet above the walkway.

5.5.4.3 Building entries may be lit with soffit, bollard, step or comparable lighting.



5.5.4.4 Step or bollard lighting shall be used to clearly illuminate level changes and handrails for stairs and ramps.

5.5.4.5 Bollards may be used to supplement and enhance other pedestrian area lighting. Bollard height shall not exceed forty-two (42) inches.

5.5.4.6 Courtyards, arcades and seating areas shall be lighted to promote pedestrian use and safety. A variety of lighting may be used to create interest and special effects in coordination with the character and function of the area.


5.5.4.7 Pedestrian lighting shall be subdued warm-white Mercury or incandescent lamps.

5.5.5 Architectural Lighting


Architectural lighting effects are encouraged to promote nighttime identity and character.

5.5.5.1 All exterior architectural lighting shall utilize indirect or hidden lighting sources. Acceptable lighting includes wall washing, overhead down lighting and interior lighting that spills outside.

5.5.5.2 Building Entry areas should be lit so as to provide a safe and inviting environment.




5.5.5.3 All building exteriors facing a freeway must have lighting levels that vary to accent the structure, texture, relief, and/or the color of the building. Lighting levels may not be flat or uniform.



5.5.6 Service Area Lighting

Service area and security lighting must be visible only within the limits of the service area.



Lighting contained within service area

5.5.6.1 Wall-mounted, security-type, service area lighting fixtures may be used only in screened service areas and only if direct light is kept within these areas. In all other areas, wall-mounted service lighting must consist of cut-off type fixtures.


5.5.6.2 Service area and security lighting may not be substituted for pedestrian, architectural or parking area lighting.

5.5.6.3 Freestanding fixtures shall be painted the same as parking area fixtures. Any wall-mounted fixtures should be compatible with the wall.



5.5.7 Accent Lighting

Unique lighting may be used to feature architectural elements, landscaping, entries and pedestrian areas, provided it is compatible with all other lighting. Accent lighting used in landscaping and pedestrian areas shall employ light sources such as Metal Halide, Quartz or L.E.D in order to accurately render plants, vegetation, and skin colors.



Landscape Lighting



5.6 On-Site Utilities

5.6.1 Utility Connections and Meters

All utility connections and meters shall be coordinated with the development of the site and should not be exposed, except where required by the utility. Utility connections should be integrated into the building or screened by landscape.

5.6.2 Pad-Mounted Transformers and Meter Box Locations

Pad-mounted transformers and/or meter box locations shall be screened from view from surrounding properties and public rights-of-way. Utilities shall be located underground, wherever possible.

5.6.3 All Equipment Shall be Internal to Buildings

All equipment shall be internal to buildings to the greatest extent possible. When unfeasible, all such equipment shall be screened and not prominently visible from public rights-of-way.

5.6.4 Utilities (including backflow preventers, detector check assemblies, transformers, etc.)

All utilities are to be installed underground. Easements for underground utilities that preclude the planting of trees may not be located where the design guidelines require the planting of trees.

Any necessary above ground equipment detector check assemblies, backflow preventers, transformers, etc., shall be screened from view from public areas by landscaping.

Domestic water service shall be extended through development sites in an easement to EMWD. The water line and easement shall be placed in easily accessible locations, such as drive aisles. Fire service and domestic water services and meters shall tie into this line. This line may become part of a loop system and the property owner may need to tie into the public mainline to provide a loop water system to provide adequate water volumes to fire hydrants.



**WORLD
LOGISTICS
CENTER®**

6.0 SUSTAINABILITY

It is the intent for this development to be a model of sustainability. While this goal is measured in many different ways and the elements of sustainability constantly evolving, it remains the intent to constantly be on the forefront of sustainability.

The following are some ways the projects can incorporate elements of sustainability:

1. Project to embrace alternate forms of transportation including, public transportation (bus), charging stations for electric cars, carpooling, and bicycles.
2. Projects are to promote the riding of bicycles, which will require racks or storage. Bicycle programs are most successful when showers and changing rooms are provided for employees.
3. Project will be required to meet the most current stormwater management programs, including on-site water capture methodologies.
4. Projects will be encouraged to reduce the 'heat-island' effect by incorporating lighter paving materials where possible and light roofing materials on all structures.
5. All site lighting is required to employ adequate shielding features to ensure zero light spill off-site.




Exhibit 6-1 *Off-site Water Management Plan*



6. Projects are to incorporate drought tolerant plant materials throughout.
7. Projects are encouraged to minimize water use in restrooms.
8. Projects are encouraged to go beyond code-required commissioning in order to ensure all mechanical and electrical equipment are operating efficiently and are not wasting energy.
9. Projects are encouraged to incorporate on-site renewable energy.
10. All projects to employ a recycling program.
11. During construction, efforts should be made to divert construction waste from landfills.
12. Projects should consider the incorporation of recycled materials where feasible.
13. Project should take measures to ensure high indoor air quality standards.
14. Care should be taken to incorporate low-emitting adhesives, paints, coatings, and flooring systems.
15. In office areas, project should make efforts to increase the amount of day-light into the interior spaces.
16. In office areas, projects should make efforts to increase the amount of view to the exterior windows.
17. During construction, incorporate the best available technology or best management practices where feasible.
18. Limit idling of engines to five minutes.
19. Utilize onsite electric power sources as much as possible to minimize the use of portable, mobile power generators.



Example of Bio-swale

7.0 SIGNAGE

Sign program to be processed separately.

7.1 Regulating Signage

All regulatory signage (traffic control, public safety, etc) shall comply with city standards.



8.0 PROJECT PHASING

8.1 OVERALL PROJECT PHASES

Based on current conditions (2012) the project is expected to be developed in two phases. Phase 1 includes the western portion of the project area extending from Redlands Blvd to Street F and from Eucalyptus to Street C/Street E. Phase 2 includes the portions of the project along SR60, Gilman Springs Road and the southerly site boundary.

Development will occur as dictated by market and other condition as determined by the developer. Notwithstanding this phasing projection, any portion of the property may be developed at any time at the owner's discretion subject to the development of infrastructure to support it. Infrastructure needs and timing will be evaluated along with subsequent development proposals.

8.2 Infrastructure Phasing

Each project within the World Logistics Center will be supported by the requisite infrastructure as needed, subject to federal, state and local codes.




Exhibit 8-1 Phasing Plan



WORLD
LOGISTICS
CENTER®

PROJECT
PHASING

9.0 FINANCING OF IMPROVEMENTS

A facilities financing program is important for implementation of the Specific Plan. The financing program needs to assure the timely financing of public streets, utilities, and other necessary capital improvements.

Financing for infrastructure improvements encompasses a variety of different mechanisms, processes, and costs that vary based on the type and purpose of an improvement, financial market conditions, debt service considerations, and agency capabilities and policies.

9.1 Capital Financing

Major infrastructure, such as water, sewers, storm drains and roads, may be financed by a special tax established through the formation of a community facilities district (CFD). Another approach may be to create a bond assessment district. Both types of financing districts require tax liens to be placed on participating properties to underwrite the sale of bonds to finance specified improvements. These mechanisms require that the facility to be financed be a public improvement and that participating properties receive a benefit from that improvement. The form of financing selected, if any, will be determined based on the type of uses and pace of development that occurs within the project. Examples include:

1. Community Facility District
2. Other forms of Assessment Districts
3. Facilities Benefit Assessment
4. City/ county direct investment
5. Reimbursement Agreements
6. State and/or federal grants and loans

The developer may elect to use private capital to finance major infrastructure improvements, as well as in-tract improvements to avoid long-term debt assessment upon buyers of improved land.



9.2 Capital Funding

The method of infrastructure funding will be determined during the engineering review of implementation development plans and in conjunction with the phasing of the infrastructure. Some possible funding mechanisms for the Specific Plan public improvements are listed below:

1. Development Impact fees
2. Transportation fees (e.g. TUMF)
3. Special taxes
4. Connection fees


9.3 Funding of Maintenance

Funding for on-going maintenance for common areas and other public improvements which may be a condition of development, such as street lights, parkway and median landscaping, other right of way improvements will be funded privately through a Property Owners' Association (POA) or publicly through the Community Services Districts (CSD) or structured as a Landscape and Lighting Maintenance District, Community Facilities District or other financing mechanism.



WORLD
LOGISTICS
CENTER®

10.0 IMPLEMENTATION



10.1 Purpose and Intent

This section contains the procedures for the processing of discretionary development applications to implement the terms of the World Logistics Specific Plan. This section provides for City review of all development within the project to ensure compliance with the provisions of the Specific Plan.

10.2 Approvals Required

All development within the World Logistics Center is subject to the approval of a Plot Plan by the City of Moreno Valley in conformance with the following procedures.

Modifications to the development standards contained in the Specific Plan may be requested by any property owner and may be approved by the City through the Plot Plan review process.

10.3 Development Review Processes

Any proposal to amend this Specific Plan shall be processed in the same manner as the original approval as determined by the Municipal Code.

10.3.1 Subdivisions

All proposed subdivisions within the World Logistics Center shall be processed in accordance with the provisions of the state Subdivision Map Act and the City of Moreno Valley Municipal Code.



10.3.2 Plot Plans

- a. All development proposals within the World Logistics Center shall be subject to the approval of a Plot Plan as described herein. Modifications to any approved uses shall be processed in the same manner. Property and building maintenance activities such as painting, site or building repairs, parking lot resurfacing/restriping, and landscape maintenance and repair, etc. are exempt from these regulations.
- b. The Plot Plan process is intended to ensure that all development proposals comply with all applicable standards and guidelines contained in this Specific Plan and are not detrimental to the public health, safety or welfare.
- c. Project comments received from the Architectural Review Committee of the World Logistics Center Property Owners' Association shall receive consideration in the Plot Plan process.
- d. Alternatives to the standards and guidelines contained within the Specific Plan may be approved through the Plot Plan process if found to be consistent with purpose and intent of the Specific Plan. Requests for such modifications may be included with Plot Plan applications for a project, or as separate applications.
- e. Plot Plan applications shall be submitted to the City of Moreno Valley in conformance with the Plot Plan procedures contained in the Municipal Code except as provided herein.
- f. Public noticing shall be in compliance with the Municipal Code.
- g. The Planning Official may approve, conditionally approve, or disapprove Plot Plan applications. Applications may be elevated to review by the Planning Commission. Reasonable conditions may be imposed to ensure compliance with applicable laws, regulations and standards or to enable the required findings to be made.
- h. Approval of a Plot Plan shall be based on all of the following findings:
 1. That the proposal is consistent with the goals, objectives, policies and programs of the Moreno Valley General Plan;
 2. That the proposed project is in compliance with the City of Moreno Valley Municipal Code



3. That the proposal is consistent with the goals, objectives, policies and programs of the World Logistics Center Specific Plan;
 4. That the proposal, together with the conditions applied thereto, will not be detrimental to the public health, safety or welfare, or be materially injurious to properties or improvements in the vicinity.
- i. Any interested party may appeal the decision of the Planning Official to the Planning Commission, subject to the provisions of the Municipal Code. Any interested party may appeal the decision of the Planning Commission to the City Council subject to the provisions of the Municipal Code. The decision of the City Council is final.

10.3.3 Additional Items

Any items not addressed in the Specific Plan shall be subject to the regulations of the Municipal Code.



11.0 SPECIAL REGULATIONS

The following regulations apply to all development within the World Logistics Center. These restrictions shall be imposed on all discretionary permits for new development projects, as applicable.

11.1 Refrigerated Warehouse Space

Refrigerated warehouse space is prohibited within the Specific Plan area.

11.2 Engine Restrictions

All medium-heavy duty trucks and heavy-heavy duty trucks entering warehouse facilities must meet or exceed 2010 engine emission standards specified in California Code of Regulations Title 13, Article 4.5, Chapter 1, Section 2025 or be powered by natural gas, electricity, or other diesel alternative. Facility operators shall maintain a log of all trucks entering the facility to document that on average, the daily truck fleet meets these emission standards. This log shall be available for inspection by City staff at any time.

11.3 On-Site Service Vehicles

The use of diesel-powered service yard vehicles (yard goats, etc.) is prohibited at all times within the Specific Plan area. Pallet jacks, forklifts, and other onsite equipment used during building operation (indoors or outdoors) shall be powered by electricity, natural gas, propane, 100 percent biodiesel or other non-diesel fuel.

11.4 Property Maintenance Equipment

Electrical power sources will be provided both indoors and outdoors to accommodate the use of electric property maintenance equipment.

11.5 Continued Agricultural Activities (Right-to-Farm)

As the World Logistics Center develops, logistics land uses will begin to locate in proximity to existing agricultural activities. Where non-agricultural uses locate near agricultural uses, there is the potential for conflict. These potential conflicts result from the inherent attributes of agricultural operations, including noise, odor, dust, smoke, operation of machinery (including aircraft), crop dusting, storage and disposal of manure, flies, rodents, chemical fertilizers, soil amendments, herbicides, pesticides and the hours of operation. As a result, such agricultural operations can become the subject of nuisance complaints and could be pressured to cease or curtail operations or may be discouraged from making farm improvements.



**WORLD
LOGISTICS
CENTER®**

**SPECIAL
REGULATIONS**

To protect the continued viability of agricultural operations within the World Logistics Center, it is the intent of this Specific Plan to limit the circumstances under which pre-existing agricultural operations may be deemed to constitute a nuisance. The intent of this policy of the Specific Plan is to balance the rights of farmers to produce agricultural commodities with the rights of non-farmers who own, occupy or use land adjacent to agricultural property. This right-to-farm policy applies to all legally established agricultural operations existing at the time of the effective date of the World Logistics Center Specific Plan.

11.6 Air Quality and Noise Assessment

To address the relationship between development areas and adjacent residential areas, all site development permit applications for properties adjacent to residentially occupied or zoned properties shall include detailed air quality and noise assessments to determine appropriate project design features to meet the performance requirements of the WLC project Environmental Impact Report.



12.0 DEFINITIONS

12kV/115 kV overhead power lines Power lines that distribute electrical power into and through the World Logistics Center project. While 12kV lines are generally placed underground, 115kV lines must remain aboveground due to the heat generated by the flow of electrical energy in the lines.

Accessory Structure A separate building, the use of which is incidental to that of the main building on the same lot or premises, and which is used exclusively by the occupant of the main building.

Ancillary Structures See accessory structure

Arterial Streets A highway intended to serve through traffic where access rights are restricted and intersections with other streets or highways are limited

Badlands A rugged, mountainous area located easterly of the City of Moreno Valley, east of Gilman Springs Road in Riverside County.

Bioretention Facility A landscape feature designed to remove silt and pollution from runoff water, generally consisting of a depressed landscaped area which slows the velocity of runoff, distributes it within the depressed area, allows the runoff to infiltrate, and directs excess runoff to downstream facilities.

Building height The vertical distance from the adjacent grade to the highest point of a building exclusive of vents, air conditioners, or other such incidental appurtenances.

CDFW California Department of Fish and Wildlife.

Class II bikeways A striped lane located along the right shoulder of a roadway designated for use by bicyclists.

CNG/LNG Abbreviation for Compressed Natural Gas (CNG) and Liquefied Natural Gas (LNG). CNG and LNG are alternative motor fuels that can be used to reduce the use of diesel fuels. LNG is natural gas that has been converted to liquid form for ease of storage or transport. CNG is natural gas that has been compressed for storage or transport in metal fuel tanks.

Collector Roads A street intended to convey traffic into and through an area from local roads to arterial streets

Detention basins A landscape feature intended to provide general flood protection by temporarily detaining runoff flows. A detention basin is designed to allow large flows of water to enter but limiting the outflow.



Eastern Municipal Water District (EMWD) The water district which provides potable water, recycled water and wastewater treatment for the World Logistics Center project.

Facades An exterior side of a building, usually, but not always, the front.

Fenestration The design of openings in a building or wall, generally including windows, doors, louvers, vents, openings, skylights, storefronts, etc.

Floor area ratio A measure of the intensity of development of a particular site. The ratio is calculated by dividing the building area by the parcel area, using the same unit of measure (acres, square feet, etc.)

Heavy truck A truck having four axles or more.

High-cube warehouse A building used for the storage and/or consolidation of manufactured goods prior to distribution to secondary retail outlets, generally 500,000 square feet or more, often divided for multiple tenants. High-cube warehouse and logistics facilities include ancillary office and maintenance space along with the outdoor storage of trucks, trailers, and shipping containers.

High-cube logistics warehouses are generally constructed with vertical-lift dock-high roll up doors to allow access for the loading and unloading of products from truck/trailers. Building interiors are typically large and open to accommodate the temporary storage and consolidation of the products to be distributed.

Highland Fairview Corporate Park A mixed use business park made up of logistics and commercial land uses located between Redlands Blvd and Theodore Street, southerly of SR60.

Impervious paved surface Artificial surfaces such as pavement (roads, sidewalks, driveways and parking lots) that are covered by impenetrable materials such as asphalt, concrete, brick, and stone. Also includes building rooftops and other structures that prevent water from penetrating into the ground surface.

Infiltration Basin A landscape feature used to manage stormwater runoff, prevent flooding and downstream erosion, and improve water quality in an adjacent drainage area.

Jobs/housing balance The ratio between the number of housing units and the number of full-time jobs in an identified geographic area. The ratio is calculated by dividing the number of full-time jobs by the number of housing units.

Lake Perris State Recreation Area A 6,675-acre state-owned recreation area including Lake Perris located southerly of the City of Moreno Valley.



Logistics The management of the flow of resources between a point of origin and a point of destination including the importation, warehousing, consolidation, repackaging and shipping of goods and materials.

Luminaire A light fixture generally affixed to a pole used in exterior areas to illuminate streets, driveways, walkways, and parking areas.

Medium trucks Trucks having three axles

Multi-Use Trails A planned city-wide system of trails that accommodate pedestrian, equestrian and bicycle users. See the Parks, Recreation and Open Space Element of the City's General Plan

Native landscape The use of plant materials found to grow naturally in an area that are adapted to a particular environment and are able to live on natural rainfall, thereby reducing the need for mechanical irrigation

Off-site Refers to those portions of the property that are not within building sites, including common areas, open space, public areas, streetscapes, etc.

Off-project Refers to areas outside of the World Logistics Center. Generally applies to infrastructure improvements needed to implement the WLC project that will extend beyond the WLC boundary.

On-site Refers to individual building sites within the World Logistics Center

San Jacinto Wildlife Area (SJWA) A 9,000-acre area owned and managed by the California Department of Fish and Game open to the public. Approximately 1,100 acres of the northerly portion of the SJWA is within the City of Moreno Valley.

Specific Plan Refers to the World Logistics Center Specific Plan which covers 2,710 acres of land in eastern Moreno Valley and functions as the land use regulations for the development of a master planned logistics campus.

Subdivision Map Act The body of law (Government Code Section 66410-66499.58) that regulates the subdivision of land in California.

Truck Routes/Truck Route Ordinance Streets that have been officially designated by for use by vehicles with a gross vehicle weight of three tons or more. See Chapter 12.36 of the Municipal Code.

World Logistics Center The project name for the development to be established under the World Logistics Center Specific Plan

Zero cut-off fixtures A lighting fixture designed to eliminate light rays from escaping above a horizontal plane.



EXHIBITS

Enlargements of Exhibits contained within the Specific Plan



WORLD
LOGISTICS
CENTER®

Exhibit 1-1 Moreno Valley Regional Map




Exhibit 1-2 Specific Plan Area




Exhibit 1-3 Surrounding Land Uses




Exhibit 1-4 Existing Fault Zones





Exhibit 2-1 Land Use Plan



Legend:

- LD Logistics Development
- LL Light Logistics
- OS Open Space
- LS Logistics Support (floating zone)
- F Fire Station Site (floating zone)



Exhibit 2-2 Fire Station Site




Exhibit 2-3 Special Edge Treatment Areas Map





Exhibit 3-1 Circulation Plan



*Street D will be designed to prohibit the use of heavy trucks.



Exhibit 3-2 Project Entries Plan




Exhibit 3-3 Arterial Streets




Exhibit 3-4a Street A




Exhibit 3-4b Street A






Exhibit 3-5 Street B



Street "B"

Exhibit 3-6 Street C, D, E



Street "C, D, E"



Exhibit 3-8 Truck Routes




Exhibit 3-9 Roundabout Diagram




Exhibit 3-10 Truck Pullout Plan




Exhibit 3-11 Truck Parking Section




Exhibit 3-12 Potential Bus Route






Exhibit 3-13 Fire Access



Emergency Access Roadway



Exhibit 3-14 Multi-Use Trail Plan



Legend:

- Conceptual Trail Alignment
- ... Existing Trail
- ★ Staging Area



Exhibit 3-15 Bicycle Circulation Plan




Exhibit 3-16 Water Facilities Master Plan




Exhibit 3-17 Wastewater Service Plan




Exhibit 3-18 Recycled Water Plan




Exhibit 3-19 Storm Drain Plan





Exhibit 3-20 Electrical Utility Plan



Legend:

- MVU Electric/Joint Trench
- - - SCE Underground
- · - SCE 115/12 KV Overhead
- · · SCE 33/12 KV Overhead



Exhibit 3-21 Gas Utility Plan




Exhibit 4-1 Special Edge Treatment Areas Design Criteria





Exhibit 4-2 Edge Exhibit Map







Exhibit 4-5, 4-6

Redlands Blvd. Section B and Plan View B





Exhibit 4-7, 4-8

Redlands Blvd. Section C and Plan View C





Exhibit 4-9, 4-10 Bay Street Section D and Plan View D





Exhibit 4-11, 4-12 Merwin Street Section E and Plan View E





Exhibit 4-13, 4-14 Merwin Street Section F and Plan View F




Exhibit 4-15 Street D Section G and Plan View G



Exhibit 4-16 SR-60 between Theodore and Gilman Springs Rd. Section H





Exhibit 4-17, 4-18 Southern Boundary Section I and Plan View I








Exhibit 4-22 Perimeter Planting Map



Perimeter Planting Legend:

-  Gilman Springs Rd. & 60 Freeway
-  Redlands Blvd., Bay Ave, Merwin St.
-  CDFG
-  Enlargement Area
-  Signage Location (Sign reads "Passenger Vehicle Entrance/Exit onto Cactus Permitted. Truck Entrance/Exit onto Cactus Prohibited.")
-  View Simulations



Exhibit 4-23 Roundabout & Entry Planting Map



Project Entry / Roundabout Plantings Legend:

- Project Entry (Orientation) / Roundabouts
- Enlargment Area
- Signage Location
 (Sign reads "Passenger Vehicle Entrance/Exit onto Cactus Permitted. Truck Entrance/Exit onto Cactus Prohibited.")



Exhibit 4-24 Streetscape Planting Map



WORLD LOGISTICS CENTER®




Exhibit 4-26 Street Lighting



Exhibit 5-1 Water Quality Management Diagram





Exhibit 5-2 Visitor Parking Plan





Legend:

-  Visitor Parking
-  Palm Courtyard
-  Employee Parking
-  Employee Gathering Area
-  Planter for Screening Truck Entries



Exhibit 5-3 Building Height Plan




Exhibit 6-1 Off-site Water Management Plan





Exhibit 8-1 Phasing Plan



Legend:

-  Phase Boundary
-  Phase Designation

